

INDEX TO DRAWINGS

CO.1	CODE INFORMATION
CIVIL	
C-1.0	CIVIL INFORMATION & GENERAL NOTES
C-2.0	EXISTING TOPOGRAPHIC PLAN
C-2.1	DEMOLITION & EROSION PROTECTION SEDIMENT CONTROL PLAN PHASE I
C-2.2	DEMOLITION & EROSION PROTECTION SEDIMENT CONTROL PLAN PHASE II
C-3.0	SITE LAYOUT PLAN
C-3.1	DIMENSIONED SITE LAYOUT PLAN
C-3.2	DIMENSIONED SITE LAYOUT PLAN
C-4.0	GRADING & DRAINAGE PLAN
C-4.1	ENLARGED GRADING PLAN
C-4.2	ENLARGED GRADING PLAN
C-5.0	SITE UTILITY PLAN
C-6.0	CONSTRUCTION DETAILS
C-6.1	CONSTRUCTION DETAILS
C-6.2	CONSTRUCTION DETAILS
STRUCTURAL	
S0.0	GENERAL NOTES
S0.1	GENERAL NOTES
S0.2	SCHEDULES AND TYPICAL DETAILS
S1.0	A/C PLE & CAP PLAN
S1.1	PILE CAP DETAILS
S2.0	GRADE BEAM PLAN
S2.1	SLAB-ON-GRADE PLAN
S2.2	FOUNDATION SECTIONS & DETAILS
S2.3	FOUNDATION SECTIONS & DETAILS
S2.4	FOUNDATION SECTIONS & DETAILS
S2.5	FOUNDATION SECTIONS & DETAILS
S3.0	MEZZANINE FRAMING PLAN - AREA A
S3.1	MEZZANINE FRAMING PLAN - AREA A
S4.0	ROOF FRAMING PLAN - AREA D
S4.1	ROOF FRAMING PLAN - AREA D
S5.0	FRAMING SECTIONS & DETAILS
S5.1	FRAMING SECTIONS & DETAILS
S5.2	FRAMING SECTIONS & DETAILS
S5.3	FRAMING SECTIONS & DETAILS
S6.0	BRACE ELEVATIONS & DETAILS
S6.1	BRACE ELEVATIONS & DETAILS
ARCHITECTURAL	
A0.1	ABBREVIATIONS, SYMBOL LEGEND, GENERAL NOTES, AND PARTITION TYPES
A1.1	FIRST FLOOR PLAN
A1.2	MEZZANINE FLOOR PLAN
A2.1	ENLARGED PLANS
A2.2	ENLARGED RESTROOM PLANS
A2.3	ENLARGED STAIRS & ELEVATOR PLANS & DETAILS
A2.4	STAIR AND ELEVATOR DETAILS
A2.5	ENLARGED PLANS, CASEWORK NOTES & DETAILS
A2.6	INTERIOR ELEVATIONS
A3.1	BUILDING ELEVATIONS
A3.2	BUILDING ELEVATIONS
A4.1	ROOF PLANS & DETAILS
A4.2	ROOF DETAILS
A5.1	BUILDING SECTIONS
A5.2	WALL SECTIONS
A6.1	DETAILS
A6.2	DETAILS
A7.1	FIRST FLOOR REFLECTED CEILING PLAN & DETAILS
A7.2	MEZZANINE CEILING PLAN & DETAILS
A8.1	DOOR SCHEDULE, DOOR, FRAME ELEVATIONS AND DETAILS
A8.2	FRAME DETAILS
A8.3	FRAME DETAILS
A9.1	STRIPPING PLANS & DETAILS
MEP	
U1.1	ELECTRICAL SITE UTILITIES PLAN
FP0.1	FIRE PROTECTION LEAD SHEET
FP1.1	FIRE PROTECTION FLOOR PLAN
FP1.2	FIRE PROTECTION MEZZANINE FLOOR PLAN
P0.1	PLUMBING LEAD SHEET
P0.2	PLUMBING SCHEDULES
P1.1	PLUMBING FLOOR PLAN - SANITARY
P1.2	PLUMBING MEZZANINE FLOOR PLAN - SANITARY
P1.3	PLUMBING FLOOR PLAN - SUPPLIES
P1.4	PLUMBING MEZZANINE PLAN - SUPPLIES
P2.1	PLUMBING ENLARGED PLANS - SANITARY
P2.2	PLUMBING ENLARGED PLANS - SUPPLIES
P3.1	PLUMBING DRAIN WASTE AND VENT DIAGRAM
P3.2	PLUMBING DRAIN WASTE AND VENT DIAGRAM
P3.3	PLUMBING DRAIN WASTE AND VENT DIAGRAM
P3.4	PLUMBING PARTIAL WATER PIPING DIAGRAM
P3.5	PLUMBING STORM WATER PIPING DIAGRAM
P3.6	PLUMBING GAS PIPING DIAGRAM
P4.1	PLUMBING DETAILS
P4.2	PLUMBING DETAILS
H0.1	HVAC LEAD SHEET
H1.1	HVAC FIRST FLOOR PLAN
H1.2	HVAC MEZZANINE PLAN
H5.1	HVAC SCHEDULES
H5.2	HVAC SCHEDULES
ME1.1	MECHANICAL/ELECTRICAL ROOF PLAN
ME2.1	MECHANICAL AND ELECTRICAL SECTIONS
E0.1	ELECTRICAL LEAD SHEET
E1.1	LIGHTING FLOOR PLAN
E1.2	LIGHTING MEZZANINE PLAN
E1.3	POWER FLOOR PLAN
E1.4	POWER MEZZANINE PLAN
E1.5	SPECIAL SYSTEMS FLOOR PLAN
E1.6	SPECIAL SYSTEMS MEZZANINE PLAN
E2.1	ELECTRICAL ENLARGED PLANS
E3.1	ELECTRICAL RISER DIAGRAM
E4.1	ELECTRICAL DETAILS
E4.2	ELECTRICAL DETAILS
E4.3	ELECTRICAL DETAILS
E4.4	ELECTRICAL DETAILS
E4.5	ELECTRICAL DETAILS
E5.1	ELECTRICAL SCHEDULES
E5.2	ELECTRICAL SCHEDULES
E5.3	ELECTRICAL SCHEDULES

OWENSBORO INDOOR SPORTS FACILITY

500 WEST THIRD STREET, OWENSBORO, KY 42301

SCB PROJECT NUMBER: 2259

OWENSBORO BID NUMBER: 4387

CONSTRUCTION DOCUMENTS

MAY 20, 2024

OWNER:

CITY OF OWENSBORO

TOM WATSON - MAYOR

MARK CASTLEN - MAYOR PRO TEM

SHARON NESMITH - COMMISSIONER

BOB GLENN - COMMISSIONER

PAMELA L. SMITH-WRIGHT - COMMISSIONER

NATE PAGAN - CITY MANAGER



SHERMAN CARTER BARNHART
ARCHITECTS, PLLC
PROJECT MANAGER: ANDREW H. OWENS, AIA, CID
144 TURNER COMMONS WAY
SUITE 110
LEXINGTON, KY 40508
PHONE: 859.224.1351
FAX: 859.224.8446
www.scbarchitects.com

CIVIL ENGINEER




AMERICAN ENGINEERS, INC.
65 ABERDEEN DRIVE
GLASGOW, KENTUCKY 42141
P (270) 651-7220

STRUCTURAL ENGINEER

LOLLEY & ASSOCIATES
309 EAST FOURTH STREET
OWENSBORO KY 42303
P (270) 683-2770


MECHANICAL/ELECTRICAL ENGINEER

MARCUM ENGINEERING
500 S 17TH STREET
PADUCAH, KY. 42003
P (270) 444-9274




FINAL DOCUMENTS

SCB PROJECT NO. 2259



1 FIRST FLOOR CODE PLAN
1/16" = 1'-0"



2 MEZZANINE CODE PLAN
1/16" = 1'-0"

SEISMIC DESIGN CRITERIA

(REFER TO SHEET SO.1 FOR ADDITIONAL INFORMATION)

RISK CATEGORY II
SITE CLASS D
SEISMIC DESIGN CATEGORY C

OCCUPANT LOAD CALCULATION

OCCUPANT LOAD CALCULATION: EXIT CAPACITY 4,077 OCCUPANTS

COURTS: 84 X 7 = 588
COURT AUXILIARY AREA 1 = 590
COURT AUXILIARY AREA 2 = 927
UNCONCENTRATED SEATING = 362
LOBBY = 693
COACHES = 8
KITCHEN = 3
STORAGE = 6
MEZZANINE UNCONCENTRATED SEATING = 613
OFFICE = 2
OFFICE = 2
OFFICE = 2
MECHANICAL = 6

TOTAL OCCUPANTS = 3,894

MAX OCCUPANTS ARE CALCULATED BASED ON VOLLEYBALL COURTS (WORST CASE)
4 TEAMS PER COURT X 11 PLAYERS PER TEAM = 44
14 COURTS X 44 = 616
1 SPECTATOR PER PLAYER = 616 X 2 = 1,232
ROUNDED TO 1,300 TO ACCOUNT FOR STAFF

ENERGY CODE COMPLIANCE

2012 ECC COMCHECK - PASS ASHRAE

SPECIAL INSPECTIONS PER CHAPTER 17 OF THE KENTUCKY BUILDING CODE

NOTE: IN ADDITION TO OTHER TESTS AND INSPECTIONS REQUIRED BY THE SPECIFICATIONS, THE OWNER SHALL PROVIDE THE SERVICES OF QUALIFIED THIRD-PARTY INSPECTORS TO PERFORM ALL REQUIRED SPECIAL INSPECTIONS AS FOLLOWS:

SECTION	ITEM	REQUIRED? _YES_ _NO_	REMARKS
1705.2	FABRICATORS	_X_	STEEL FABRICATION SPECIAL INSPECTION IS REQUIRED IF THE FABRICATOR IS NOT A.I.S.C. OR AWS CERTIFIED.
1705.2.1	STEEL	_X_	STRUCTURAL STEEL AND JOISTS, PER TABLE 1705.2.2
1705.3	CONCRETE	_X_	PER TABLE 1705.3
1705.4	MASONRY	_X_	PER TMS 402 / TMS 602
1705.5	WOOD	_X_	NONE
1705.6	SOILS	_X_	PER TABLE 1705.6
1705.7	DRIVEN DEEP FOUNDATIONS	_X_	NONE
1705.8	CAST-IN-PLACE DEEP FOUNDATIONS	_X_	NONE
1705.9	HELICAL PILE FOUNDATIONS	_X_	NONE
1705.10	INSPECTIONS FOR WIND RESISTANCE	_X_	Vand 120 MPH, WIND EXPOSURE CAT. "C"
1705.11	INSPECTIONS FOR SEISMIC RESISTANCE	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12	TESTING & QUALIFICATION FOR SEISMIC RESISTANCE	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12.1	STRUCTURAL STEEL	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12.2	STRUCTURAL WOOD	_X_	NONE
1705.12.3	COLD-FORMED STEEL LIGHT-FRAME CONST.	_X_	NONE
1705.12.4	DESIGNATED SEISMIC SYSTEMS	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12.5	ARCHITECTURAL COMPONENTS	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12.6	PLUMBING, MECHANICAL AND ELECTRICAL COMPONENTS	_X_	SEISMIC DESIGN CATEGORY "D"
1705.12.9	COLD-FORMED STEEL SPECIAL BOLTED MOMENT FRAMES	_X_	NONE
1705.14	SPRAYED FIRE-RESISTANT MATERIALS	_X_	NONE
1705.15	MASTIC AND INTUMESCENT FIRE-RESISTANT COATINGS	_X_	NONE
1705.16	EXTERIOR INSULATION AND FINISH SYSTEMS (EIFS)	_X_	NONE
1705.17	FIRE-RESISTANT PENETRATIONS AND JOINTS	_X_	RISK CATEGORY II
1705.18	TESTING FOR SMOKE CONTROL	_X_	NONE

(NOTE: REFER TO STRUCTURAL SHEETS FOR STRUCTURAL QUALITY ASSURANCE)

CODE COMPLIANCE INFORMATION

GENERAL INFORMATION :
CODE: KENTUCKY BUILDING CODE 2018, THIRD EDITION
USE GROUP: A-4 (ASSEMBLY)
CONSTRUCTION TYPE: TYPE II B
FIRE PROTECTION: FULLY SPRINKLERED PER NFPA 13, VOICE ALARM
BUILDING HEIGHT CALCULATIONS:
ALLOWABLE HEIGHT = 1 STORY / 65'-0" (TABLE 507.4)
ACTUAL BUILDING HEIGHT = 1 STORY + MEZZANINE / 42'-8"

BUILDING AREA:
ALLOWABLE AREA = UNLIMITED PER SECTION 507.4 (SECTION 507.4)
* BUILDING HAS 60' PUBLIC WAY
DISTANCE TO LOT LINE + PUBLIC RIGHT-OF-WAY = 60' + ON ALL SIDES

BUILDING AREA:
FIRST FLOOR: 77,326 SQ. FT.
MEZZANINE: 13,021 SQ. FT.
EXTERIOR COVERED TERRACE: 2,642 SQ. FT.
ALTERNATE STORAGE ROOM: 1,610 SQ. FT.
TOTAL AREA: 94,599 SQ. FT.


TRAVEL DISTANCES:
TRAVEL DISTANCE TO EXIT:
ACTUAL MAXIMUM TRAVEL DISTANCE: 228'-0"
(MAXIMUM ALLOWABLE TRAVEL DISTANCE: 250'-0" (PER TABLE 1017.2))

MINIMUM FIRE RESISTANCE RATINGS (PER TABLES 601 AND 602)

STRUCTURAL FRAME	: 0 HR
BEARING WALLS EXTERIOR	: 0 HR
BEARING WALLS INTERIOR	: 0 HR
NON-BEARING EXTERIOR WALLS	: 0 HR > 30' DISTANCE
NON-BEARING INTERIOR WALLS	: 0 HR
FLOOR CONSTRUCTION	: 0 HR
ROOF CONSTRUCTION (< 20 FT. ABOVE FLOOR)	: 0 HR
ROOF CONSTRUCTION (> 20 FT. ABOVE FLOOR)	: 0 HR

FINAL DOCUMENTS

SHERMAN
CARTER
BARNHART
ARCHITECTS



OWENSBORO INDOOR SPORTS
FACILITY
500 WEST THIRD STREET
OWENSBORO, KY 42301

CODE INFORMATION

JOB NO. 2259
DATE MAY 20, 2024
DRAWN AN, CRG, DB

CHECKED BKL, DB, AHO

COPYRIGHT © 2024
SHERMAN CARTER BARNHART
ARCHITECTS, PLLC

REVISIONS

No.	Description	Date

SHEET

C0.1



SEISMIC DESIGN CRITERIA			
(REFER TO SHEET 50.1 FOR ADDITIONAL INFORMATION)			
RISK CATEGORY	II		
SITE CLASS	D		
SEISMIC DESIGN CATEGORY	C		
OCCUPANT LOAD CALCULATION			
OCCUPANT LOAD CALCULATION:		EXIT CAPACITY	4,077 OCCUPANTS
COURTS: 84 X 7 = 588 COURT AUXILIARY AREA 1 = 590 COURT AUXILIARY AREA 2 = 927 UNCONCENTRATED SEATING = 362 LOBBY = 693 COACHES = 8 KITCHEN = 3 STORAGE = 6 MEZZANINE UNCONCENTRATED SEATING = 613 OFFICE = 2 OFFICE = 2 OFFICE = 2 MECHANICAL = 6			
TOTAL OCCUPANTS = 3,804			
MAX OCCUPANTS ARE CALCULATED BASED ON VOLLEYBALL COURTS (WORST CASE) 4 TEAMS PER COURT X 11 PLAYERS PER TEAM = 44 14 COURTS X 44 = 616 1 SPECTATOR PER PLAYER = 616 X 2 = 1,232 ROUNDED TO 1,300 TO ACCOUNT FOR STAFF			
ENERGY CODE COMPLIANCE			
2012 IECC COMCHECK - PASS ASHRAE			
SPECIAL INSPECTIONS PER CHAPTER 17 OF THE KENTUCKY BUILDING CODE			
NOTE: IN ADDITION TO OTHER TESTS AND INSPECTIONS REQUIRED BY THE SPECIFICATIONS, THE OWNER SHALL PROVIDE THE SERVICES OF QUALIFIED THIRD-PARTY INSPECTORS TO PERFORM ALL REQUIRED SPECIAL INSPECTIONS AS FOLLOWS.			
SECTION	ITEM	REQUIRED? _ YES_ _ NO_	REMARKS
1705.2	FABRICATORS	_ X_ _	STEEL FABRICATION SPECIAL INSPECTION IS REQUIRED IF THE FABRICATOR IS NOT A I.S.C. OR AWS CERTIFIED.
1705.2.1	STEEL	_ X_ _	STRUCTURAL STEEL AND JOISTS, PER TABLE 1705.2.2
1705.3	CONCRETE	_ X_ _	PER TABLE 1705.3
1705.4	MASONRY	_ X_ _	PER TMS 402 / TMS 602
1705.5	WOOD	_ _ X_ _	NONE
1705.6	SOILS	_ X_ _	PER TABLE 1705.6
1705.7	DRIVEN DEEP FOUNDATION	_ _ X_ _	NONE
1705.8	CAST-IN-PLACE DEEP FOUNDATIONS	_ _ X_ _	NONE
1705.9	HELICAL PILE FOUNDATIONS	_ _ X_ _	NONE
1705.10	INSPECTIONS FOR WIND RESISTANCE	_ _ X_ _	WIND 120 MPH. WIND EXPOSURE CAT. "C"
1705.11	INSPECTIONS FOR SEISMIC RESISTANCE	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12	TESTING & QUALIFICATION FOR SEISMIC RESISTANCE	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12.1	STRUCTURAL STEEL	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12.2	STRUCTURAL WOOD	_ _ X_ _	NONE
1705.12.3	COLD-FORMED STEEL LIGHT-FRAME CONST.	_ _ X_ _	NONE
1705.12.4	DESIGNATED SEISMIC SYSTEMS	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12.5	ARCHITECTURAL COMPONENTS	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12.6	PLUMBING, MECHANICAL AND ELECTRICAL COMPONENTS	_ X_ _	SEISMIC DESIGN CATEGORY "D"
1705.12.9	COLD-FORMED STEEL SPECIAL BOLTED MOMENT FRAMES	_ _ X_ _	NONE
1705.14	SPRAYED FIRE-RESISTANT MATERIALS	_ _ X_ _	NONE
1705.15	MASTIC AND INTUMESCENT FIRE-RESISTANT COATINGS	_ _ X_ _	NONE
1705.16	EXTERIOR INSULATION AND FINISH SYSTEMS (EIFS)	_ _ X_ _	NONE
1705.17	FIRE-RESISTANT PENETRATIONS AND JOINTS	_ _ X_ _	RISK CATEGORY II
1705.18	TESTING FOR SMOKE CONTROL	_ _ X_ _	NONE
NOTE: REFER TO STRUCTURAL SHEETS FOR STRUCTURAL QUALITY ASSURANCE			
CODE COMPLIANCE INFORMATION			
GENERAL INFORMATION :		BUILDING AREA:	
CODE: KENTUCKY BUILDING CODE 2018, THIRD EDITION		ALLOWABLE AREA (SECTION 507.4)	= UNLIMITED PER SECTION 507.4
USE GROUP: A-4 (ASSEMBLY)		* BUILDING HAS 60' PUBLIC WAY DISTANCE TO LOT LINE + PUBLIC RIGHT-OF-WAY = 60' ON ALL SIDES	
CONSTRUCTION TYPE: TYPE II B			
FIRE PROTECTION: FULLY SPRINKLERED PER NFPA 13, VOICE ALARM		BUILDING AREA:	
BUILDING HEIGHT CALCULATIONS :		FIRST FLOOR:	77,326 SQ. FT.
		MEZZANINE:	33,032 SQ. FT.
		EXTERIOR COVERED TERRACE:	2,842 SQ. FT.
		ALTERNATE STORAGE ROOM:	1,610 SQ. FT.
ALLOWABLE HEIGHT = 1 STORY / 65'-0" (TABLE 507.4)		TOTAL AREA:	94,599 SQ. FT.
ACTUAL BUILDING HEIGHT = 1 STORY + MEZZANINE / 42'-8"			
TRAVEL DISTANCES :			
TRAVEL DISTANCE TO EXT:			
ACTUAL MAXIMUM TRAVEL DISTANCE: 228'-0"			
(MAXIMUM ALLOWABLE TRAVEL DISTANCE: 250'-0" (PER TABLE 1017.2)			
MINIMUM FIRE RESISTANCE RATINGS (PER TABLES 601 AND 602)			
STRUCTURAL FRAME	:	0 HR	
BEARING WALLS EXTERIOR	:	0 HR	
BEARING WALLS INTERIOR	:	0 HR	
NON-BEARING EXTERIOR WALLS	:	0 HR > 30' DISTANCE	
NON-BEARING INTERIOR WALLS	:	0 HR	
FLOOR CONSTRUCTION	:	0 HR	
ROOF CONSTRUCTION (< 20 FT. ABOVE FLOOR)	:	0 HR	
ROOF CONSTRUCTION (> 20 FT. ABOVE FLOOR)	:	0 HR	

GENERAL NOTES

1. PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL PERMITTING AUTHORITIES.
2. NO GRADING, STRIPPING, EXCAVATION, FILLING OR OTHER DISTURBANCE OF THE NATURAL GROUND COVER SHALL TAKE PLACE UNTIL PROPOSED SOIL EROSION CONTROL PLAN HAS BEEN APPROVED AND IN PLACE.
3. ALL DIMENSIONS INVOLVING CURBS ARE SHOWN TO FACE OF CURB, UNLESS NOTED OTHERWISE.
4. IN THE CASE OF CONFLICT BETWEEN THIS DRAWING AND ANY OTHER DRAWING AND/OR SPECIFICATIONS, THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED FOR CLARIFICATION.
5. THE CONTRACTOR SHALL BID AND PERFORM THE WORK IN ACCORDANCE WITH ALL LOCAL, STATE AND NATIONAL CODES AND THE REQUIREMENTS OF LOCAL UTILITY COMPANIES.
6. IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND WILL NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING ALL BARRICADES, WARNING SIGNS, FLASHING LIGHTS AND THE TRAFFIC CONTROL DEVICES DURING CONSTRUCTION. CONTRACTOR SHALL COMPLY WITH OSHA REGULATIONS AND SAFETY REQUIREMENTS.
7. THE CONTRACTOR IS RESPONSIBLE FOR THE SAFETY OF ALL VEHICLE TRAFFIC IN AND AROUND THE CONSTRUCTION AREA.
8. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4" TOPSOIL, SEEDED, MULCHED AND WATERED AS NECESSARY TO PROVIDE SUBSTANTIAL GRASS COVER.
9. ALL PAVEMENT MARKINGS INCLUDING STRIPES, DIRECTIONAL ARROWS, ETC., SHALL BE WHITE PAINT (TWO COATS). HANDICAP SYMBOL COLORS SHALL BE PER LOCAL CODE. APPROVED EXTERIOR PAINTS ARE AS FOLLOWS:
- PRATT AND LAMBERT TRAFFIC PAINT
SHERWIN-WILLIAMS PRO-MARK TRAFFIC MARKING
-PAINT B29 SERIES
GLIDDEN ROMARK TRAFFIC PAINT
PPG ZONE AND TRAFFIC MARKING PAINT
FOY-JOHNSTON TRAFFIC PAINT 9862
10. ANY DAMAGE TO JAMES T. ROGERS DRIVE OR 31-E DUE TO CONSTRUCTION ACTIVITIES SHALL BE REPAIRED TO NEW CONDITION AT NO COST TO THE OWNER(S). EXTENTS OF DAMAGE AND REPAIR SHALL BE COORDINATED AND APPROVED BY THE OWNER(S) AND ENGINEER PRIOR TO CONSTRUCTION.
11. ROCK REMOVAL SHALL BE UNCLASSIFIED. ROCK REMOVAL REQUIREMENTS ARE OUTLINED IN SPECIFICATION SECTION 312200 EARTHWORK.
12. CLARIFICATION: IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PERMIT ANY WORK WITHIN THE TRIBUTARY TO SOUTH FORK BEAVER CREEK ALONG 31-E, A BLUELINE STREAM ON USGS MAPPING. IF CONSTRUCTION ACTIVITIES EXCEED THE CURRENT PIPE EXTENSION SCOPE WHICH, AS DESIGNED, IS BELOW THE REGULATED TRIGGER FOR STREAM DISTURBANCE OF 0.03 ACRES OF IMPACT, ABOVE WHICH REQUIRING AN INDIVIDUAL PERMIT PER GUIDELINES OUTLINED BY US ARMY CORPS OF ENGINEERS.
13. CLARIFICATION: THE METHOD FOR TREE CLEARING, GRUBBING, BURNING AND/OR REMOVAL WILL BE AT THE DISCRETION OF THE CONTRACTOR AND HIS/HER SUBCONTRACTORS PER PERMITTING REQUIREMENTS FOR STATE, FEDERAL AND/OR LOCAL (CITY-COUNTY AND FIRE DEPT.) REVIEW PRIOR TO BEGINNING CONSTRUCTION. OPEN BURNING IS REGULATED BY 401 KAR 63.005.

GRADING AND DRAINAGE NOTES:

1. CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES HAVING UNDERGROUND UTILITIES ON SITE OR IN RIGHT-OF-WAY PRIOR TO EXCAVATION. CONTRACTOR SHALL NOTIFY KY-811 48 HOURS PRIOR TO EXCAVATION.
2. SITE GRADING SHALL NOT PROCEED UNTIL EROSION CONTROL MEASURES HAVE BEEN INSTALLED.
3. NO CUT OR FILL SLOPES SHALL BE CONSTRUCTED STEEPER THAN 3H:1V UNLESS SPECIFICALLY NOTED ON THE PLANS.
4. SITE GRADES AROUND PAVEMENT AND BUILDING AREAS SHALL BE GRADED DURING CONSTRUCTION TO PREVENT PONDING. ANY SURFACE WATER ACCUMULATION IN THE PAVEMENT AND BUILDING AREAS SHALL BE DRAINED IMMEDIATELY TO AVOID SATURATION OF THE SUBGRADE SOILS.
5. ALL EXCAVATIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST OSHA GUIDELINES AS MANDATED IN CURRENT FEDERAL, STATE AND LOCAL REGULATIONS. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE IN PROVIDING SAFE WORKING CONDITIONS IN CONNECTION WITH ANY EXCAVATION WORK.
6. SUITABLE FILL MATERIAL PLACED UNDER BUILDING AREAS SHALL BE PLACED IN MAXIMUM 8-INCH (LOOSE THICKNESS) VERTICAL LIFTS, WITH EACH LIFT BEING COMPACTED TO A MINIMUM OF 98 PERCENT OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY, AT A MOISTURE CONTENT WITHIN 2 PERCENT OF OPTIMUM. THE COMPACTION REQUIREMENT MAY BE REDUCED TO 95 PERCENT IN PROPOSED PAVED AREAS, AND TO 92 PERCENT IN PROPOSED LANDSCAPE AREAS. WETTING OR DRYING OF THE SOILS MAY BE NECESSARY TO ACHIEVE A MOISTURE CONTENT SUITABLE FOR COMPACTION. REPRESENTATIVE AND ADEQUATE FIELD DENSITY TESTING SHALL BE PERFORMED BY INDEPENDENT TESTING AGENCY PROVIDED BY OWNER TO VERIFY THAT COMPACTION REQUIREMENTS HAVE BEEN MET.
7. STONE BASES SHOULD BE COMPACTED TO A DENSITY SATISFACTORY TO ENGINEER, TYPICALLY 94% OF SOLID VOLUME OR BY TEST STRIP METHODS.
8. ALL EXISTING STRUCTURES, UNLESS OTHERWISE NOTED TO REMAIN, FENCING, TREES, ETC., WITHIN CONSTRUCTION AREA SHALL BE REMOVED AND DISPOSED OF OFF SITE.
9. GRADE LINES SHOWN ARE FINISHED GRADE. CONTRACTOR SHOULD SEE DETAIL SHEET FOR APPROPRIATE PAVEMENT TYPE TO DETERMINE SUB-GRADE ELEVATIONS FOR PAVING AREAS.
10. CONTRACTOR IS ADVISED THAT FINAL GRADING AND CURB PLACEMENT SHALL BE COMPLETED TO ACCOMMODATE THE FOLLOWING:
- A. NO WATER WILL POND AT POINTS WHERE LANDSCAPE ISLANDS EXTEND INTO PARKING FIELDS.
- B. SPACES DESIGNATED FOR HANDICAP PARKING AND ACCESS AISLE SHALL HAVE A FINAL SLOPE AFTER PAVING IS COMPLETED OF NOT MORE THAN 2.0%. IF EITHER OF THESE ITEMS ARE NOT CONSTRUCTED AS OUTLINED ABOVE, REWORK WILL BE PROVIDED BY THE CONTRACTOR TO CORRECT DEFICIENCIES AT THE CONTRACTORS EXPENSE.
11. THE CONTRACTOR SHALL VERIFY POSITIVE FLOW FOR ALL STORM SEWER SYSTEMS. DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY.

UTILITY NOTES:

1. THE CONTRACTOR IS ADVISED THAT ALL EXISTING UTILITIES SHOWN WERE FIELD SURVEYED BASED ON LOCATIONS PROVIDED BY EACH UTILITY COMPANY. OTHER UTILITIES MAY EXIST THAT ARE UNMAPPED. THE CONTRACTOR IS ADVISED TO FIELD VERIFY ALL UNDERGROUND UTILITIES BY CONTACTING THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS TO EXCAVATION.
2. ALL UTILITIES TO BE CONSTRUCTED TO WITHIN 5' OF BUILDING.
3. BACK FILL OF ALL TRENCHES BENEATH STRUCTURES AND/OR PAVEMENT SHALL BE CRUSHED STONE OR SIMILAR MATERIAL AS APPROVED BY ENGINEER.
4. CONTRACTORS ARE ADVISED TO COORDINATE INSTALLATION OF ALL BURIED CONDUITS AND LINES SUCH THAT LINES WHICH CROSS ARE LAD BEGINNING WITH DEEPEST LINE FIRST.
5. DEPTH OF WATERLINE SHALL BE ADJUSTED AS REQUIRED TO ALLOW FOR SPECIFIED PLACEMENT OF SANITARY AND STORM SEWERS, BUT IN NO CASE LESS THAN 30".
6. TAPPING AND INSPECTION FEES TO BE PAID BY CONTRACTOR, METER FEES TO BE PAID BY OWNER.
7. CONTRACTOR SHALL COORDINATE WATER AND SEWER SERVICES CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL UTILITY CO.
8. ALL TRENCHING, PIPE LAYING AND BACK FILLING SHALL BE IN ACCORDANCE WITH FEDERAL OSHA REGULATIONS.
9. CONTRACTOR SHALL OBTAIN APPROVAL FROM ALL GOVERNING AGENCIES HAVING JURISDICTION OF UTILITY SYSTEMS PRIOR TO INSTALLATION.
10. ALL GATE VALVES SHALL BE PROVIDED WITH VALVE BOX IN ACCORDANCE WITH WATER UTILITY STANDARDS.
11. THRUST BLOCKS SHALL BE PROVIDED AT ALL BENDS, TEES, AND FIRE HYDRANTS AND SHALL BE CONSTRUCTED ACCORDING TO WATER DEPARTMENT STANDARDS. 12. ALL WATER AND SANITARY SEWER SERVICE LINES TO THE BUILDING(S) SHALL BE PROVIDED WITH A TEMPORARY PLUG (FOR OTHERS TO REMOVE AND EXTEND AS NECESSARY).
12. THE CONTRACTOR SHALL FLUSH AND TEST ALL NEW UTILITY LINES ACCORDING TO THE STATE DIVISION OF WATER OR LOCAL WATER CO. STANDARDS.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS AND ELEVATIONS OF EXISTING AND PROPOSED UTILITIES PRIOR TO CONSTRUCTION. ANY CONFLICTS DISCOVERED AFTER CONSTRUCTION HAS BEGUN, SHALL BE CORRECTED AT CONTRACTORS EXPENSE.
14. THE MINIMUM HORIZONTAL SEPARATION BETWEEN WATER AND SEWER LINES IS TEN FEET OUTSIDE DIAMETER TO OUTSIDE DIAMETER. THE MINIMUM VERTICAL SEPARATION IS EIGHTEEN INCHES.
15. BEFORE YOU DIG... CONTRACTOR SHALL NOTIFY BUD, 1-800-752-6007 48 HOURS PRIOR TO EXCAVATION, TO LOCATE AND FLAG ALL UNDERGROUND UTILITIES WITHIN THE PROPOSED RIGHT OF WAY.

JOB SITE SAFETY

1. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR JOB SITE SAFETY DURING CONSTRUCTION. JOB SITE SAFETY IS OUTSIDE THE SCOPE OF WORK OF AMERICAN ENGINEERS, INC. AND SHERMAN CARTER BARNHART AND NEITHER THE PROFESSIONAL ACTIVITIES OR THE PRESENCE OF AEI OR SUBCONSULTANTS AT THE CONSTRUCTION SITE SHALL RELIEVE THE CONTRACTOR OR ANY OTHER ENTITY OF THEIR OBLIGATION, DUTIES, AND RESPONSIBILITIES INCLUDED, BUT NOT LIMITED TO: CONSTRUCTION MEANS, METHODS, SEQUENCES, TECHNIQUES, TO PROCEDURES NECESSARY FOR PERFORMING SUPERINTENDING OR COORDINATING ALL PORTIONS OF THE WORK OF CONSTRUCTION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND ANY HEALTH AND SAFETY PRECAUTIONS REQUIRED BY GOOD CONSTRUCTION PRACTICES OR ANY REGULATORY AGENCIES. ANYONE USING INFORMATION FROM THESE PLANS ACKNOWLEDGES AND WARRANTS THAT AEI IS NOT RESPONSIBLE FOR SITE SAFETY IN ANY WAY.

ACCESSIBILITY INFORMATION

1. ALL RAMPS SIDEWALKS AND APRONS SHALL BE COMPLIANT WITH THE MOST CURRENT DEPARTMENT OF JUSTICE ADA REQUIREMENTS (ADA STANDARDS FOR ACCESSIBLE DESIGN, CODE OF FEDERAL REGULATIONS, CURRENT EDITION).
2. THE ELEVATION OF ALL EXTERIOR WALKS AND SLABS SHALL BE ADA COMPLIANT AND AT 1/4" BELOW FINISH FLOOR AT ALL DOORS. AN ADA LANDING SHALL BE PROVIDED AT ALL DOORS.
3. ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL BE ADA COMPLIANT, NOT TO EXCEED 2% IN ANY DIRECTION.

ABBREVIATIONS

A	AREA	(N)	NORTH
ALT	ALTERNATE	OC	ON CENTER
AMP	AMPERE	OSHA	OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION
ARCH	ARCHITECTURAL	PC	POINT OF CURVATURE
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	PH	POLYETHYLENE
BC	BACK OF CURB	PHASE	PHASE
BIT	BITUMINOUS PAVEMENT	PSI	POUNDS PER SQUARE INCH
BM	BENCH MARK	PT	POINT OF TANGENCY
C	CONDUIT	PVC	POLYVINYL CHLORIDE
CAL	CALIPER	PVMT	PAVEMENT
CB	CATCH BASIN	R	RADIUS
CFH	CUBIC FEET PER HOUR	RCP	REINFORCED CONCRETE PIPE
CL	CURB ISLAND	RE	REFERENCE
CIR	CIRCUIT	REQD	REQUIRED
CONC	CONCRETE	RHW	RIGHT-OF-WAY
DBI	DITCH BOTTOM INLET	EW	EXISTING UNDERGROUND ELECTRICAL LINE
DIA	DIAMETER	(S)	SOUTH
E	EAST	SAN	SANITARY SEWER
E.I.F.S.	EXTERIOR INSULATION FINISHING SYSTEM	SB	SOIL BORING
EL	ELEVATION	SF	SQUARE FEET
EQ	EQUIVALENT	SQ	SQUARE
ES	END SECTION	STM	STORM SEWER
ETC	ETCETERA	STRUC	STRUCTURE
FF	FIRE HYDRANT	TC	TOP OF CURB
FF	FINISHED FLOOR	TEL	TELEPHONE
FT	FOOT SQUARE	TP	TOP OF PAVEMENT
GRD	GROUND	TRNF	TRANSFORMER
GP	GUTTER PAN	TS	TOP OF SLAB
GPD	GALLONS PER DAY	TY	TYPICAL
GPM	GALLONS PER MINUTE	UC	UTILITY CROSSING
GVABOX	GATE VALVE AND BOX	UD	UNDER DRAIN
HC	HIGH CAPACITY	W	WIRE
HD	HEAVY DUTY	(W)	WEST
HEX	HEIGHT	W	WITH
HT	HEIGHT	WC	WATER COLUMN
IE	INVERT ELEVATION	WTR	WATER
KVA	KILOVAOLT AMPERE	WWF	WELDED WIRE FABRIC
LBS	POUNDS		
LD	LIGHT DUTY		
LED	LIGHT EMITTING DIODE		
LF	LINEAR FEET		
LG	LARGE		
MANUF	MANUFACTURE		
MATL	MATERIAL		
MAX	MAXIMUM		
MECH	MECHANICAL		
MIN	MINIMUM		
MH	MANHOLE		

ENGINEER
RICHARD TUTT, P.E.
AMERICAN ENGINEERS, INC.
65 ABERDEEN DRIVE
GLASGOW, KENTUCKY 42141
(270) 651-7220

SURVEYOR
JEFFREY C. SMITH, P.L.S.
AMERICAN ENGINEERS, INC.
65 ABERDEEN DRIVE
GLASGOW, KENTUCKY 42141
(270) 651-7220

LEGEND / ABBREVIATIONS

LEGEND

	RIGHT OF WAY		TELEPHONE PEDESTAL
	PROPERTY LINE		EXISTING TREE
	ADJOINING PROPERTY LINE		SPRINKLER HEAD
	EXISTING EASEMENT		EXISTING SIGN
	EXISTING 1' CONTOUR		BENCH MARK
	EXISTING 5' CONTOUR		DOWNSPOUT
	EXISTING CONCRETE CURB		ELECTRIC JUNCTION BOX
	W/ DROP CURB		EXISTING GUIDE WIRE
	EDGE OF PAVEMENT		EXISTING CLEANOUT
	EXISTING OVERHEAD WIRES		EXISTING BOLLARD
	RIGHT-OF-WAY RETAINING WALL		
	EXISTING WATER LINE		
	EXISTING UNDERGROUND TELEPHONE LINE		
	EXISTING SANITARY SEWER STRUCTURE		
	EXISTING STORM STRUCTURE		
	EXISTING GASLINE		
	EXISTING FENCE		
	EXISTING FIRE HYDRANT		
	WATER VALVE		
	WATER METER		
	GAS METER		
	EXISTING POWER POLE		
	EXISTING LIGHT POLE (2 LIGHTS)		
	EXISTING SANITARY SEWER MANHOLE		
	EXISTING STORM SEWER MANHOLE		
	DROP BOX INLET (DBI)		
	EXISTING TRANSFORMER PAD		

ZONING

OMPC:
200 EAST 3RD STREET
OWENSBORO, KY 42302
TELEPHONE: 270-687-8650

BUILDING PERMITS

OMPC:
200 EAST 3RD STREET
OWENSBORO, KY 42302
TELEPHONE: 270-687-8650

GAS

ATMOS ENERGY
3275 HIGHLAND POINTE DR.
OWENSBORO, KY 42303
270-685-8000

TELEPHONE

AT&T
5115 FEDERICA STREET
OWENSBORO, KY 42301
TELEPHONE: 270-685-8405

ELECTRIC

OMU
2070 TAMARACK RD.
OWENSBORO, KY 42301
270-926-3200

SEWER

RWRA
2101 GRIMES AVE.
OWENSBORO, KY 42303
270-687-8450

WATER

OMU
2070 TAMARACK RD.
OWENSBORO, KY 42301
270-926-3200

TRANSPORTATION

KYTC DISTRICT 2
1840 NORTH MAIN STREET
MADISONVILLE, KY 42431
TELEPHONE: 270-824-7080

CITY OF OWENSBORO


CITY ENGINEERING OFFICE
11410 W. 5TH STREET
OWENSBORO, KY 42301
270-687-8641

AGENCIES

INDEX OF SHEETS


	C-1.0	COVER SHEET & GENERAL NOTES
	C-2.0	EXISTING TOPO
	C-2.1	DEMOLITION PLAN & EPSC PLAN PHASE I
	C-2.2	EPSC PLAN PHASE II
	C-3.0	SITE LAYOUT PLAN
	C-3.1	DIMENSIONED SITE LAYOUT PLAN
	C-3.2	DIMENSIONED SITE LAYOUT PLAN
	C-4.0	GRADING & DRAINAGE PLAN
	C-4.1	ENLARGED GRADING PLAN
	C-4.2	ENLARGED GRADING PLAN
	C-5.0	UTILITY PLAN
	C-6.0	CONSTRUCTION DETAILS
	C-6.1	CONSTRUCTION DETAILS
	C-6.2	CONSTRUCTION DETAILS

SHEET INDEX LEGEND



BEFORE YOU DIG

The contractor is instructed to call 1-800-752-6007 to reach KY 811, the one-call system for information on the location of existing underground utilities. The call is to be placed a minimum of two (2) and no more than ten (10) business days prior to excavation. The contractor should be aware that owners of underground facilities are not required to be members of the KY 811 one-call Before-U-Dig (BUD) service. The contractor must coordinate excavation with the utility owners, including those whom do not subscribe to KY 811. It may be necessary for the contractor to contact the County Court Clerk to determine what utility companies have facilities in the area.



**OWENSBORO INDOOR
SPORTS FACILITY**
500 W 3RD ST, OWENSBORO, KY 42301

**CIVIL INFORMATION &
GENERAL NOTES**

JOB NO. 223-061

DATE 05-20-24

DRAWN M. ALLEN

CHECKED R. TUTT


COPYRIGHT © 2024
AMERICAN ENGINEERS, INC.

REVISIONS

No.	Description	Date

SHEET

C-1.0



SEE SHEET C-3.1

SEE SHEET C-3.2

CONSTRUCTION LEGEND


- CONCRETE PAVEMENT / SIDEWALK
- HEAVY DUTY ASPHALT PAVEMENT
- EDGE KEY
- TACTILE WARNING STRIP

GENERAL NOTES

- LOT LIGHTING CONCRETE FOOTINGS TO CONFORM WITH THE SOILS REPORT RECOMMENDATIONS FOR THIS PARTICULAR SITE.
- ANY WORK PERFORMED IN THE R.O.W. SHALL BE PER CITY GUIDELINES AND STANDARD SPECIFICATIONS.
- ALL EXPOSED CONCRETE CORNERS TO BE CHAMFERED AND/OR TO HAVE RADII.
- ALL EXPOSED CONCRETE CURBS, SIDEWALK, SLABS, PAVEMENT, AND FOUNDATIONS SHALL BE TREATED WITH AN AQURON CONCRETE TREATMENT AS MANUFACTURED BY AQURON, OR APPROVED EQUAL.
- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR DEMOLITION OF ANY REMAINING SITE IMPROVEMENTS PRIOR TO CONSTRUCTION.
- ALL JOINTS WHERE NEW PAVEMENT ADJOINS EXISTING PAVEMENT SHALL BE SAW CUT, TO INSURE A STRAIGHT CLEAN LINE, OR WILL BE CARRIED TO THE NEXT EXPANSION JOINT ON DOT R.O.W. WHERE FEASIBLE.
- ALL CURB RADI SHALL BE 5' (U.N.O.).
- ALL CURB FACES AND PAVEMENT ELEVATION SHALL MATCH ADJOINING CURBING AND PAVEMENT EXACTLY.
- STABILIZE AND GRASS ALL SLOPES TO PREVENT EROSION.
- ALL DIMENSIONS ARE GIVEN TO THE FACE OF CURB.
- CONTRACTOR TO USE EXISTING TOPOGRAPHIC PLAN IN CONJUNCTION WITH THIS SITE PLAN FOR LOCATION AND SIZES OF EXISTING FEATURES.
- UNDERGROUND UTILITIES ARE BASED ON FIELD SURVEY. OTHER UTILITIES MAY EXIST. AND ARE UNMAAPPED. CONTRACTOR TO FIELD VERIFY UTILITIES IN PROJECT AREA. CONTRACTOR WILL REPLACE/REPAIR ALL UTILITIES DAMAGED DURING CONSTRUCTION.
- PROVIDE 1/2" EXPANSION JOINT MATERIAL WITH SEALANT WHERE CONCRETE CURBS, SIDEWALK, OR PAVING ABUTS STORM STRUCTURES, BUILDINGS, ETC.
- AT END OF PROJECT, CONTRACTOR SHALL REMOVE ALL CONSTRUCTION FENCING, EROSION CONTROL STRUCTURES, AND OTHER TEMPORARY SERVICES ON SITE.
- ALL 90° CONCRETE PAVEMENT CORNERS SHALL RECEIVE 12" BY 12" CHAMFER.
- ALL DISTURBED AREAS AND PARKING LOT ISLANDS SHALL RECEIVE A MINIMUM OF 6" TOPSOIL, SEEDED AND WATERED AS NECESSARY TO PROVIDE SUBSTANTIAL GRASS COVER.
- ANY DAMAGE TO EXISTING STREETS/ROADS DUE TO CONSTRUCTION ACTIVITIES SHALL BE REPAIRED TO NEW CONDITION AT NO COST TO THE OWNER(S). EXTENTS OF DAMAGE AND REPAIR SHALL BE COORDINATED AND APPROVED BY THE OWNER(S) AND ENGINEER PRIOR TO CONSTRUCTION.
- RE-STRIP PAVEMENT MARKINGS TO MATCH EXISTING CONDITIONS.
- REFER TO OWENSBORO METROPOLITAN PUBLIC IMPROVEMENT SPECIFICATIONS FOR ALL WORK IN THE RIGHT-OF-WAY.



KEY NOTES

- HEAVY DUTY CONCRETE PAVEMENT. RE: DETAIL 1 / C-6.0
- ADA COMPLIANT SIDEWALK. RE: DETAIL 2 / C-6.0
- ADA COMPLIANT SIDEWALK WITH PAVER FRAME. RE: DETAIL 3 / C-6.0
- ADA COMPLIANT RAMP. RE: DETAIL 2 / C-6.0 AND SHEET C-4.0 GRADING PLAN
- CONCRETE STEPS. RE: DETAIL 5 / C-6.0
- HANDRAIL. RE: DETAIL 6 / C-6.0
- HEADER CURB. RE: DETAIL 7 / C-6.0
- R/W CURB AND GUTTER. RE: DETAIL 11 / C-6.0
- R/W SIDEWALK RAMP. RE: DETAIL 12 / C-6.0 AND SHEET C-4.0 GRADING PLAN
- R/W TACTILE WARNING STRIP. RE: DETAIL 1 / C-6.1
- R/W CONCRETE ENTRANCE. RE: DETAIL 2 / C-6.1
- HEAVY DUTY ASPHALT PAVEMENT. RE: DETAIL 8 / C-6.0
- EDGE KEY. RE: DETAIL 4 / C-6.0
- DUMPSTER ENCLOSURE. RE: DETAIL 3 / C-6.1
- STREET OUT CUP REPAIR. RE: DETAIL 4 / C-6.1



JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT
COPYRIGHT © 2024 AMERICAN ENGINEERS, INC.	

REVISIONS		
No.	Description	Date



CONSTRUCTION LEGEND

-  INLET PROTECTION
RE: DETAIL 9 / C-6.0
-  FIBER ROLL
RE: DETAIL 10 / C-6.0

EPSC & CONSTRUCTION PHASE 2

1. THE FOLLOWING PHASING IS SUGGESTED BUT IS SUBJECT TO CHANGE UPON THE SELECTION OF A SITE CONTRACTOR THAT MAY PROPOSE A MORE FEASIBLE PLAN. ANY CHANGES TO THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL PLAN WILL RESULT IN REQUIRING REDLINE PLANS TO BE SUBMITTED FOR REVIEW AND APPROVAL BY SOWLING GREEN PUBLIC WORK.
2. MAINTAIN EXISTING INLET PROTECTION.
3. MAINTAIN EXISTING TEMPORARY SILT FENCE PROTECTION.
4. MAINTAIN EXISTING CONSTRUCTION ENTRANCE.
5. BEGIN EARTHWORK.
6. CONSTRUCT BUILDING.
7. INSTALL STORM DRAINAGE SYSTEM.
8. INSTALL NEW INLET PROTECTION.
9. INSTALL UTILITIES.
10. INSTALL CURBING, PAVEMENT AND SIDEWALKS.
11. REMOVE TEMPORARY EROSION CONTROL DEVICES AFTER SUBSTANTIAL COMPLETION.




JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT

COPYRIGHT © 2024
AMERICAN ENGINEERS, INC.

REVISIONS		
No.	Description	Date

SHEET

THE DEMOLITION PLAN IS NOT ALL-INCLUSIVE. THE CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL OF ALL EXISTING ITEMS, INCLUDING BUT NOT LIMITED TO PAVEMENT, SIDEWALKS, CURBING, UNDERGROUND AND ABOVE GROUND UTILITIES, STORM STRUCTURES AND PIPE, NECESSARY TO ACCOMPLISH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



LEGEND
SYMBOLS THAT MAY APPEAR ON DRAWING

SITE DEMOLITION - REMOVE ASPHALT, CONCRETE, SIDEWALK, UTILITIES, DROP BOX INLETS, BUILDING, ECT. NOT LIMITED TO ITEMS LISTED.

CURB & GUTTER REMOVAL

CONSTRUCTION LEGEND

INLET PROTECTION
RE: DETAIL 9 / C-6.0

FIBER ROLL
RE: DETAIL 10 / C-6.0

EROSION PREVENTION MAINTENANCE SCHEDULE:

ALL BMP'S NEED TO BE MAINTAINED EVERY SEVEN (7) DAYS, AFTER EVERY STORM EVENT THAT EQUALS OR EXCEEDS 1/2 INCH PRECIPITATION, OR AFTER HEAVY USE.

- SILT FENCE:**
1. REMOVE SEDIMENT FROM THE UP-SLOPE FACE OF THE FENCE BEFORE IT ACCUMULATES TO A HEIGHT EQUAL TO 1/3 THE HEIGHT OF THE FENCE.
 2. IF FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED SECTION OF FENCE IMMEDIATELY.
 3. TAKE CARE TO AVOID UNDERMINING OR DAMAGING THE FENCE WHEN CLEANING OUT SEDIMENT.
 4. REMOVE THE FENCE AFTER ITS CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED. REMOVE THE FENCE AND SEDIMENT DEPOSITS, BRING THE DISTURBED AREA TO GRADE, AND STABILIZE IT USING THE APPROPRIATE PERMANENT STABILIZATION METHOD.

- TEMPORARY CONSTRUCTION ENTRANCE:**
1. CHECK FOR MUD AND SEDIMENT BUILDUP AND PAD INTEGRITY.
 2. MADE DAILY INSPECTIONS DURING WET WEATHER. MAINTENANCE IS REQUIRED MORE FREQUENTLY IN WET CONDITIONS.
 3. RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
 4. WASH OR REPLACE STONE AS NEEDED AND AS DIRECTED BY THE INSPECTOR. THE STONE IN THE ENTRANCE SHOULD BE WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFFSITE BY VEHICLES. FREQUENT WASHING WILL EXTEND THE USEFUL LIFE OF THE STONE.
 5. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. REPAIR ANY BROKEN PAVEMENT IMMEDIATELY.
 6. REMOVE TEMPORARY CONSTRUCTION ENTRANCE AS SOON AS THEY ARE NO LONGER NEEDED TO PROVIDE ACCESS TO THE SITE.

- STONE BAG INLET PROTECTION:**
1. REMOVE SEDIMENT FROM THE UP-SLOPE FACE OF THE STONE BAGS SILT CHECK BEFORE IT ACCUMULATES TO A HEIGHT EQUAL TO 1/3 THE HEIGHT OF THE FENCE.
 2. IF STONE BAGS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE OR DAMAGES OCCUR, REPLACE THE AFFECTED STONE BAGS IMMEDIATELY.
 3. TAKE CARE TO AVOID UNDERMINING OR DAMAGING THE STONE BAGS WHEN CLEANING OUT SEDIMENT.
 4. REMOVE THE STONE BAGS AFTER ITS CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED. REMOVE THE STONE BAGS AND SEDIMENT DEPOSITS, BRING THE DISTURBED AREA TO GRADE, AND STABILIZE IT USING THE APPROPRIATE PERMANENT STABILIZATION METHOD.

EROSION PREVENTION & SEDIMENT CONTROL NOTES:

1. THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PLAN SHALL BE IMPLEMENTED PRIOR TO ANY LAND DISTURBING ACTIVITIES ON THE CONSTRUCTION SITE. ANY MODIFICATIONS TO THE APPROVED EPSC PLAN MUST BE REVIEWED AND APPROVED BY BOWLING GREEN PUBLIC WORKS OFFICE. EPSC BMP'S SHALL BE INSTALL PER THE PLAN AND BOWLING GREEN PUBLIC WORK STANDARDS.
2. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOIL TRACKED ONTO THE ROADWAY SHALL BE REMOVED DAILY.
3. SOIL STOCKPILES SHALL BE LOCATED AWAY FROM STREAMS, PONDS, SWALES AND CATCH BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED THROUGH THE USE OF SILT FENCE.
4. WHERE CONSTRUCTION OR LAND DISTURBANCE ACTIVITY WILL OR HAS TEMPORARILY CEASED ON ANY PORTION OF A SITE, TEMPORARY SITE STABILIZATION MEASURES SHALL BE REQUIRED AS SOON AS PRACTICABLE, BUT NO LATER THAN 14 CALENDAR DAYS AFTER ACTIVITY HAS CEASED.
5. SEDIMENT-LOADED GROUNDWATER ENCOUNTERED DURING TRENCHING, BORING OR OTHER EXCAVATION ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPED DEVICE PRIOR TO BEING DISCHARGED INTO A STREAM, POND, SWALE OR CATCH BASIN.

EPSC & CONSTRUCTION PHASE 1

1. THE FOLLOWING PHASING IS SUGGESTED BUT IS SUBJECT TO CHANGE UPON THE SELECTION OF A SITE CONTRACTOR THAT MAY PROPOSE A MORE FEASIBLE PLAN. ANY CHANGES TO THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL PLAN WILL RESULT IN REQUIRING REDLINE PLANS TO BE SUBMITTED FOR REVIEW AND APPROVAL BY BOWLING GREEN PUBLIC WORK.
2. INSTALL INLET PROTECTION.
3. INSTALL TEMPORARY SILT FENCE PROTECTION.
4. INSTALL CONSTRUCTION ENTRANCE.
5. BEGIN EARTHWORK.

SITE DEMOLITION GENERAL NOTES:

1. THE CONTRACTOR SHALL CONFORM TO LOCAL CODES, OBTAIN ALL PERMITS AND GIVE ALL NOTICES REQUIRED FOR EXECUTION OF THE WORK.
2. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL CHARTED AND UNCHARTED UTILITIES. TAKE CARE TO PROTECT UTILITIES THAT ARE TO REMAIN, REPAIR ANY DAMAGE ACCORDING TO LOCAL STANDARDS AND AT THE CONTRACTOR'S EXPENSE. COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY.
3. PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL VERIFY THE LIMITS OF DEMOLITION WITH THE OWNER'S REPRESENTATIVE.
4. SAW CUT TO PROVIDE A CLEAN EDGE IN AREAS WHERE EXISTING PAVEMENT, WALKS, OR CURBS ARE TO BE REMOVED. THE EXTENT OF PAVEMENT DEMOLITION SHALL BE COORDINATED WITH THE LIMIT OF NEW IMPROVEMENTS ON THE PROPOSED SITE IMPROVEMENT PLANS.
5. THE CONTRACTOR SHALL COORDINATE PHASING OF THE DEMOLITION WITH THE OWNER'S REPRESENTATIVE AND LOCAL GOVERNING AGENCY PRIOR TO BEGINNING WORK. DISRUPTION OF EXISTING UTILITY SERVICES AND TRAFFIC PATTERNS SHALL BE MINIMIZED TO THE EXTENT POSSIBLE AND INITIATED ONLY AFTER APPROVAL BY THE LOCAL GOVERNING AGENCY AND THE UTILITY COMPANIES.
6. CAVITIES CREATED DURING DEMOLITION SHALL BE SUITABLY BACKFILLED AND COMPACTED IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEERING RECOMMENDATIONS AND SPECIFICATIONS.
7. THE CONTRACTOR SHALL USE WATER SPRINKLING AND/OR OTHER SUITABLE METHODS AS NEEDED TO CONTROL DUST CAUSED BY THE DEMOLITION WORK.
8. THE CONTRACTOR IS RESPONSIBLE FOR ALL ABOVE GROUND AND BELOW GROUND DEMOLITION AND REMOVAL NECESSARY TO ACCOMPLISH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.
9. THE CONTRACTOR SHALL PRESERVE AND PROTECT SURVEY CONTROL POINTS AND SHALL BE RESPONSIBLE FOR REPLACEMENT OF ANY DISTURBED CONTROL POINTS AT NO COST TO THE OWNER.
10. SITE LIGHTING DEMOLITION AND LAYOUT SHALL BE COORDINATED WITH THE ELECTRICAL DRAWINGS.
11. RELOCATION OF EXISTING PLANT MATERIALS SHALL BE COORDINATED WITH THE OWNER AND RELOCATED TO A DESIGNATED AREA ON SITE.
12. EXISTING SHRUBS TO BE PRESERVED ARE TO BE BARRICADED BEFORE BEGINNING CONSTRUCTION.
13. THE CONTRACTOR SHALL INCORPORATE INTO HIS WORK ANY ISOLATION VALVES OR TEMPORARY PLUGS REQUIRED TO CONSTRUCT NEW UTILITY LINES WHILE DEMOLISHING EXISTING UTILITY LINES.
14. REFER TO CONSTRUCTION MANAGER SITE PHASING REQUIREMENTS FOR ADDITIONAL INFORMATION.
15. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4" TOPSOIL, SEEDED, MULCHED AND WATERED AS NECESSARY TO PROVIDE SUBSTANTIAL GRASS COVER.
16. ANY DAMAGE FROM CONSTRUCTION ACTIVITIES WITHIN PROPERTY LINES SHALL BE REPAIRED TO NEW CONDITION AT NO COST TO THE OWNERS. EXTENTS OF DAMAGE AND REPAIR SHALL BE COORDINATED AND APPROVED BY THE OWNER(S) AND ENGINEER PRIOR TO CONSTRUCTION.


40 20 0 40 80

JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT

COPYRIGHT © 2024
AMERICAN ENGINEERS, INC.

REVISIONS		
No.	Description	Date

SHEET




- GENERAL NOTES**
- THIS SURVEY IS SUBJECT TO ANY AND ALL LEGAL EASEMENTS AND RIGHT OF WAYS RECORDED OR UNRECORDED, INCLUDING BUT NOT LIMITED TO THOSE SHOWN HEREON.
 - THIS SURVEY IS SUBJECT TO ANY AND ALL FACTS THAT MAY BE DISCLOSED BY A FULL AND ACCURATE TITLE SEARCH.
 - THE LOCATION OF THE UNDERGROUND AND ABOVE GROUND UTILITIES SHOWN HEREON ARE BASED ON THE FIELD LOCATION OF FOUND VISIBLE STRUCTURES OR AS FLAGGED AND/OR PAINTED BY THEIR RESPECTIVE UTILITY COMPANIES. OTHER UTILITIES MAY EXIST. NO GUARANTEE IS EXPRESSED OR IMPLIED AS TO THE ACTUAL LOCATION AND/OR EXISTENCE OF SAID UNDERGROUND UTILITIES ON THIS SITE.
 - THE PROPERTY SHOWN HEREON IS SUBJECT TO THE RULES, REGULATIONS, SETBACKS AND ORDINANCES SET FORTH BY THE LOCAL PLANNING COMMISSION.
 - GPS NOTE:
85 % OF SURVEY WAS PERFORMED USING TRIMBLE - R10 - DUAL FREQUENCY GPS UNITS UTILIZING REAL TIME KINEMATIC SURVEYING TECHNIQUES. WITH AN UNADJUSTED PRECISION TO CONTROL POINTS BEING LESS THAN 0.04' OR BEING GREATER THAN 1 : 10,000.
 - FLOOD ZONE NOTE:
THIS PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD ZONE AS INDICATED BY FLOOD INSURANCE RATE MAPS COMMUNITY PANEL NO. 21059C0138D, EFFECTIVE DATE OF APRIL 16, 2009.
 - THIS IS NOT A BOUNDARY SURVEY. NOT TO BE RECORDED OR USED FOR THE TRANSFER OF REAL PROPERTY. LOT LINES ARE SHOWN FOR INDEXING PURPOSES ONLY AND SHOULD NOT BE CONSTRUED TO BE TRUE AND ACCURATE.

PARCEL OWNER AND SOURCE OF TITLE FOR SURVEY
CITY OF OWENSBORO
101 FOURTH STREET, PO BOX 10003
OWENSBORO, KY 42302

PVA#
006-02-02-001.00, 006-02-02-003.00, 006-02-02-004.00
006-02-02-005.00, 006-02-02-006.00, 006-02-02-007.00
006-02-02-008.00, 006-02-02-009.00, 006-02-02-010.00
006-02-02-011.00, 006-02-02-012.00

DEED BOOK 1077 PAGE 350



BASIS OF BEARINGS AND ELEVATIONS
THE BASIS OF THE BEARINGS SHOWN HEREON WERE BASED ON GRID NORTH AS IT RELATES TO THE KENTUCKY STATE PLANE COORDINATE SYSTEM (SINGLE ZONE) NAD83. ALL ELEVATIONS SHOWN HEREON WERE BASED ON NAVD83 (GEOID 18), AS OBSERVED VIA RTK BASED OFF OF NGS CORS NETWORK, FEBRUARY, 2023.

1' CONTOUR INTERVAL

STORM MANHOLE
RIM ELEV.: 392.86'
12" PVC ELEV.: 386.09'
18" PVC ELEV.: 385.07'
F.L. ELEV.: 384.05'

STORM MANHOLE
RIM ELEV.: 392.14'
F.L. N/A

CURB BOX INLET
RIM ELEV.: 391.58'
F.L. ELEV.: 386.23'

PLANTER

EXISTING BUILDING

ASPHALT

BUILDING HT. 410.04'

F.F.E. 394.04'

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT

ASPHALT


ASPHALT

ASPHALT

ASPHALT


ASPHALT

Point	North	East	Elevation	Notes	Description
1	392.86'	386.09'	385.07'		STORM MANHOLE




LEGEND	
SYMBOLS THAT MAY APPEAR ON DRAWING	
[Symbol]	RIGHT OF WAY
[Symbol]	PROPERTY LINE
[Symbol]	ADJOINING PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	EXISTING 1' CONTOUR
[Symbol]	EXISTING 5' CONTOUR
[Symbol]	EXISTING CONCRETE CURB
[Symbol]	EXISTING OVERHEAD WIRE
[Symbol]	EDGE OF PAVEMENT
[Symbol]	EXISTING UNDERGROUND ELECTRICAL LINE
[Symbol]	EXISTING UNDERGROUND TELEPHONE LINE
[Symbol]	EXISTING SANITARY SEWER
[Symbol]	EXISTING GASLINE
[Symbol]	EXISTING FENCE
[Symbol]	EXISTING FIRE HYDRANT
[Symbol]	WATER VALVE
[Symbol]	WATER METER
[Symbol]	GAS METER
[Symbol]	EXISTING POWER POLE
[Symbol]	EXISTING LIGHT POLE (CLUSTERS)
[Symbol]	EXISTING SANITARY SEWER MANHOLE
[Symbol]	EXISTING STORM SEWER MANHOLE
[Symbol]	DRAINAGE BOX INLET (DBI)
[Symbol]	EXISTING TRANSFORMER PAD
[Symbol]	TELEPHONE PEDESTAL
[Symbol]	EXISTING TREE
[Symbol]	SPRINKLER HEAD
[Symbol]	EXISTING SIGN
[Symbol]	BORER HOLE
[Symbol]	DOWNSPOUT
[Symbol]	ELECTRIC JUNCTION BOX
[Symbol]	EXISTING GROUND WIRE
[Symbol]	EXISTING CLEANDOUT
[Symbol]	EXISTING BOLLARD
[Symbol]	EXISTING STRUCTURE (AS NOTED)
[Symbol]	EXISTING CONCRETE
[Symbol]	EXISTING GRAVEL
[Symbol]	EXISTING RIP RAP
[Symbol]	EXISTING LANDSCAPED AREA

PRELIMINARY




JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT
COPYRIGHT © 2024 AMERICAN ENGINEERS, INC.	

REVISIONS		
No.	Description	Date





SEE SHEET C-3.2



JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT
COPYRIGHT © 2024 AMERICAN ENGINEERS, INC.	

REVISIONS		
No.	Description	Date



10 5 0 10 20

SEE SHEET C-3.1

JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT
COPYRIGHT © 2024 AMERICAN ENGINEERS, INC.	



REVISIONS		
No.	Description	Date

SYMBOLS THAT MAY APPEAR ON THIS PLAN	
SYMBOL	ABBREVIATION
XXXX FG	FINISH GRADE
XXXX EX	TIE TO EXISTING
XXXX TC	TOP OF CURB
XXXX BC	BOTTOM OF CURB
XXXX TS	TOP OF SIDEWALK
XXXX BS	BOTTOM OF SIDEWALK
XXXX TW	TOP OF WALL
XXXX BW	BOTTOM OF WALL


ADA GENERAL ACCESSIBILITY GUIDELINE NOTES:

THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ADA COMPATIBILITY PRIOR TO CONSTRUCTION. IF ANY DISCREPANCIES ARISE, CONTACT THE ENGINEER IMMEDIATELY.

1.	CURB RAMP: MAXIMUM RUNNING SLOPE TARGET MAX. RUNNING SLOPE	8.33% 7.5%-8.0%
2.	ACCESSIBLE PARKING PAD: MAX. CROSS SLOPE IN ANY DIRECTION TARGET MAX. CROSS SLOPE IN ANY DIRECTION	2.0% 1.5%-1.9%
3.	CROSSWALKS AND ACCESSIBLE ROUTES: MAX. RUNNING SLOPE TARGET MAX. RUNNING SLOPE MAX. CROSS SLOPE TARGET MAX. CROSS SLOPE	5.0% 4.5%-4.9% 2.0% 1.5%-1.9%
4.	CLEAR FLOOR AREAS AT DOOR OPENINGS: MAX. RUNNING SLOPE TARGET MAX. RUNNING SLOPE MAX. CROSS SLOPE TARGET MAX. CROSS SLOPE	2.0% 1.5%-1.9% 2.0% 1.5%-1.9%






SEE SHEET C-4.2



SYMBOLS THAT MAY APPEAR ON THIS PLAN	
SYMBOL	ABBREVIATION
XXXX FG	FINISH GRADE
XXXX EX	TIE TO EXISTING
XXXX TC	TOP OF CURB
XXXX BC	BOTTOM OF CURB
XXXX TS	TOP OF SIDEWALK
XXXX BS	BOTTOM OF SIDEWALK
XXXX TW	TOP OF WALL
XXXX BW	BOTTOM OF WALL

ADA GENERAL ACCESSIBILITY GUIDELINE NOTES:		
THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ADA COMPATIBILITY PRIOR TO CONSTRUCTION. IF ANY DISCREPANCIES ARISE, CONTACT THE ENGINEER IMMEDIATELY.		
1. CURB RAMP:	MAXIMUM RUNNING SLOPE	8.33%
	TARGET MAX. RUNNING SLOPE	7.5%-8.0%
2. ACCESSIBLE PARKING PAD:	MAX. CROSS SLOPE IN ANY DIRECTION	2.0%
	TARGET MAX. CROSS SLOPE IN ANY DIRECTION	1.5%-1.9%
3. CROSSWALKS AND ACCESSIBLE ROUTES:	MAX. RUNNING SLOPE	5.0%
	TARGET MAX. RUNNING SLOPE	4.5%-4.9%
	MAX. CROSS SLOPE	2.0%
	TARGET MAX. CROSS SLOPE	1.5%-1.9%
4. CLEAR FLOOR AREAS AT DOOR OPENINGS:	MAX. RUNNING SLOPE	2.0%
	TARGET MAX. RUNNING SLOPE	1.5%-1.9%
	MAX. CROSS SLOPE	2.0%
	TARGET MAX. CROSS SLOPE	1.5%-1.9%





PROPOSED UTILITY LEGEND	
SS	PROPOSED SANITARY SEWER
W	PROPOSED WATER SERVICE
E	PROPOSED UNDERGROUND ELECTRIC
G	PROPOSED UNDERGROUND GAS
T	PROPOSED COMMUNICATIONS

- UTILITY NOTES:
- THE CONTRACTOR IS ADVISED THAT ALL EXISTING UTILITIES SHOWN WERE FIELD SURVEYED BASED ON LOCATIONS PROVIDED BY EACH UTILITY COMPANY. OTHER UTILITIES MAY EXIST THAT ARE UNMAAPPED. THE CONTRACTOR IS ADVISED TO FIELD VERIFY ALL UNDERGROUND UTILITIES BY CONTACTING THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS TO EXCAVATION.
 - ALL UTILITIES TO BE CONSTRUCTED TO WITHIN 5' OF BUILDING.
 - BACK FILL OF ALL TRENCHES BENEATH STRUCTURES AND/OR PAVEMENT SHALL BE CRUSHED STONE OR SIMILAR MATERIAL AS APPROVED BY ENGINEER.
 - CONTRACTORS ARE ADVISED TO COORDINATE INSTALLATION OF ALL BURIED CONDUITS AND LINES SUCH THAT LINES WHICH CROSS ARE LAID BEGINNING WITH DEEPEST LINE FIRST.
 - DEPTH OF WATERLINE SHALL BE ADJUSTED AS REQUIRED TO ALLOW FOR SPECIFIED PLACEMENT OF SANITARY AND STORM SEWERS, BUT IN NO CASE LESS THAN 30"
 - TAPPING AND INSPECTION FEES TO BE PAID BY CONTRACTOR, METER FEES TO BE PAID BY OWNER.
 - CONTRACTOR SHALL COORDINATE WATER AND SEWER SERVICES CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL UTILITY COMPANY.
 - ALL TRENCHING, PIPE LAYING AND BACK FILLING SHALL BE IN ACCORDANCE WITH FEDERAL OSHA REGULATIONS.
 - CONTRACTOR SHALL OBTAIN APPROVAL FROM ALL GOVERNING AGENCIES HAVING JURISDICTION OF UTILITY SYSTEMS PRIOR TO INSTALLATION.
 - ALL GATE VALVES SHALL BE PROVIDED WITH VALVE BOX IN ACCORDANCE WITH WATER UTILITY STANDARDS.
 - THRUST BLOCKS SHALL BE PROVIDED AT ALL BENDS, TEES, AND FIRE HYDRANTS AND SHALL BE CONSTRUCTED ACCORDING TO WATER DEPARTMENT STANDARDS.
 - ALL WATER AND SANITARY SEWER SERVICE LINES TO THE BUILDING(S) SHALL BE PROVIDED WITH A TEMPORARY PLUG (FOR OTHERS TO REMOVE AND EXTEND AS NECESSARY).
 - THE CONTRACTOR SHALL FLUSH AND TEST ALL NEW UTILITY LINES ACCORDING TO THE STATE DIVISION OF WATER OR LOCAL WATER CO. STANDARDS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS AND ELEVATIONS OF EXISTING AND PROPOSED UTILITIES PRIOR TO CONSTRUCTION. ANY CONFLICTS DISCOVERED AFTER CONSTRUCTION HAS BEGUN, SHALL BE CORRECTED AT CONTRACTORS EXPENSE.
 - THE MINIMUM HORIZONTAL SEPARATION BETWEEN WATER AND SEWER LINES IS TEN FEET OUTSIDE DIAMETER TO OUTSIDE DIAMETER. THE MINIMUM VERTICAL SEPARATION IS EIGHTEEN INCHES.
 - BEFORE YOU DIG, CONTRACTOR SHALL NOTIFY BUD, 1-800-752-6077 48 HOURS PRIOR TO EXCAVATION, TO LOCATE AND FLAG ALL UNDERGROUND UTILITIES WITHIN THE PROPOSED RIGHT OF WAY.
 - REFER TO OWENSBORO METROPOLITAN, PUBLIC IMPROVEMENT SPECIFICATIONS FOR ELECTRICAL AND WATER STANDARD DETAILS.
 - REFER TO REGIONAL WATER RESOURCE AGENCY FOR SANITARY SEWER STANDARD DETAILS.

- KEY NOTES
- APPROXIMATE LOCATION OF GAS TIE-IN
 - GAS LINE INSTALLED BY ATMOS ENERGY. TRENCHING AND SLEEVEING BY CONTRACTOR
 - APPROXIMATE LOCATION OF WATER HOT TAP
 - 3" TRAFFIC RATED WATER METER
 - 3" SDR-21 DOMESTIC WATER SUPPLY
 - 6" C-800 FIRE SUPPRESSION LINE
 - SANITARY SEWER MANHOLE
 - 4" SDR-35 SANITARY SEWER LINE @ 1.25% MINIMUM. REFER TO PLUMBING PLANS FOR CONTINUATION
 - 6" SDR-35 SANITARY SEWER LINE @ 1.25% MINIMUM. REFER TO PLUMBING PLANS FOR CONTINUATION
 - GREASE INTERCEPTOR. REFER TO PLUMBING PLANS FOR CONTINUATION
 - SANITARY SEWER CLEANOUT





JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT

COPYRIGHT © 2024
AMERICAN ENGINEERS, INC.

REVISIONS		
No.	Description	Date


SHEET

C-5.0



**SIDEWALK
DETAIL**


N.T.S.



**SIDEWALK WITH PAVER FRAME
DETAIL**

N.T.S.

3




EDGE KEY
DETAIL
N.T.S.



**CONCRETE STEPS
DETAIL**


N.T.S.



**HANDRAIL
DETAIL**

N.T.S.

6




**HEADER CURB
DETAIL**

N.T.S.




7




HEAVY DUTY BITUMINOUS PAVEMENT
DETAIL

N.T.S.

8




INLET PROTECTION
DETAIL
N.T.S.



**FIBER ROLL
DETAIL**

N.T.S.


10














**R/W CURB & GUTTER
DETAIL**

N.T.S.

11



R/W CURB RAMP
DETAIL
N.T.S.




ACCEPTABLE CASTINGS
FOR CURB INLETS

- NEENAH R-3246
- EAST JORDAN 7030 M-4
- JOHN BOUCHARD & SONS 3080


ACCEPTABLE CASTINGS
FOR VALLEY INLETS
(IN DRIVEWAYS)

- NEENAH R-3510
- EAST JORDAN 7370



INLET CASTING DETAIL

INLET CASTING SHALL BE
SEALED TO THE INLET BOX
WITH A MASTIC COMPOUND
AND MORTARED ON.



INLET BOX DETAIL

NOTES:
CLASS A CONCRETE
2" MIN. CONCRETE COVER
OPENINGS FOR PIPE AS REQD.
REINF. #5 REBAR @ 12" C.C. EA. WAY
6" THICK BASE SLAB
WEIGHT: BASE - 3600lbs./max
RISER - 900lbs./vert.ft.
FOR PIPES LARGER THAN 30", ADDITIONAL
DESIGN IS REQUIRED

OWENSBORO METROPOLITAN PUBLIC IMPROVEMENT SPECIFICATIONS
CHAPTER 7 STORM SEWERS
INLET BOX AND CASTING DETAILS
EXHIBIT NO. 7-5
NOT TO SCALE



JOB NO.	223-061
DATE	05-20-24
DRAWN	M. ALLEN
CHECKED	R. TUTT
COPYRIGHT © 2024 AMERICAN ENGINEERS, INC.	

REVISIONS		
No.	Description	Date

CODES AND SPECIFICATIONS

- A. GENERAL BUILDING CODE
- The Contract Documents are based on the requirements of the Kentucky Building Code, latest Edition. This code shall include all addenda and amendments in force at the date of these documents unless noted otherwise.
- B. CONCRETE CODES
- The design, detailing and erection of all concrete elements shall additionally be based on the following:
- Building Code Requirements for Reinforced Concrete (ACI 318-11), Specifications for Structural Concrete for Buildings (ACI 301) and all other Committee Reports and Specifications as published by the American Concrete Institute including all amendments and addenda in force at the date of these documents.
 - Manual of Standard Practice, latest edition, as published by the Concrete Reinforcing Steel Institute (CRSI) including all supplements in force at the date of these documents.
 - Structural Welding Code - Steel, AWS D1.4 latest edition, American Welding Society.
- C. MASONRY CODES
- The design, detailing and erection of all masonry elements shall be based on the following:
- Building Code Requirements for Masonry Structures (ACI 530-11).
- D. STRUCTURAL STEEL CODES
- The design, detailing and erection of all structural steel elements shall additionally be based on the following:
- Specification for Structural Steel Buildings - Allowable And Plastic Design, latest edition as published by the American Institute of Steel Construction (AISC).
 - Specification for Structural Joints Using ASTM A325 or A490 Bolts, latest edition, as approved by the Research Council on Structural Connections.
 - Structural Welding Code - Steel, AWS/AIWS D1.1, American Welding Society.
- All Codes and Specifications listed above shall include all amendments and addenda in force at the date of these documents.

- E. PRECAST AND PRECAST-PRESTRESSED REQUIREMENTS
- The design, detailing and erection of precast and precast prestressed elements shall additionally be based on the recommendations presented in the PCI Design Handbook, latest edition, as published by the Prestressed Concrete Institute.
- F. CONFLICTS IN STRUCTURAL REQUIREMENTS
- Where conflict exists between the various publications as specified herein, the strictest requirements of the various publications shall govern. Where conflict exists between the various parts of the Contract Documents (Architectural Drawings, Structural Drawings, General Notes, Specifications) the strictest requirements shall govern.

DESIGN CRITERIA

- A. DEAD LOADS
1. Dead Loads. Dead load materials assumed in the design are shown on the Architectural and Structural Drawings. Any changes in construction materials from those shown on the architectural or structural drawings shall be reported by the General Contractor to the Structural Engineer for verification of load carrying capacity of the structure.
- B. LIVE LOADS
1. Principal design live loads are shown below. All live loads whether listed below or not are based on the requirements of the building code cited in these General Notes above unless the loads listed below are greater. Live load reduction as specified herein has been used unless specifically excluded below. Design live loads are based on the more restrictive of the uniform load listed below or the concentrated load listed acting over an area 2.5 square feet.

CATEGORY	MINIMUM FLOOR LIVE LOAD UNIFORM LOAD (PSF)	CONCENTRATED LOAD (LB)
Roof	20	
Kitchens, Stairs and Lobbies	50	
Storage and Mechanical	120	
Typical 14 and 20 ft. Plots	100	
NOTE: See Sheet LP-1.4 for additional information regarding Live Loads.		

- C. SNOW LOADS
- Snow loads used in the strength design of the building frame shall be based on the general building code referenced above. The snow load constants are as follows:
- P_g = Ground Snow Load = 10 PSF
- P_f = Flat Roof Snow Load = 10 PSF
- P_u = Importance Factor = 1.1
- C_e = Exposure Factor = 1.0
- C_d = Wind Directionality Factor = 1.0
- P_u = Flat Roof Snow Load = 11.6 PSF

- D. RAIN LOADS
- Load = 5 PSF

- E. WIND LOADS
- Wind pressures used in the strength design of the building frame shall be based on the general building code referenced above. The wind load constants are as follows:
- Basic Wind Speed: 115 MPH (Ultimate)
- Exposure: B
- I = Importance Factor = 1.1
- C_e = Exposure Factor = 1.0
- C_d = Wind Directionality Factor = 1.0
- P_u = Flat Roof Snow Load = 11.6 PSF

		(AREA D)		
		ROOF	Surface Pressure (PSF)	Surface Pressure (PSF)
Negative Zone 1	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Negative Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Positive All Zones	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 3	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
		(AREA A, B, C)		
		ROOF	Surface Pressure (PSF)	Surface Pressure (PSF)
Negative Zone 1	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Negative Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Positive All Zones	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 3	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
		(AREA A, B, C)		
		WALL	Surface Pressure (PSF)	Surface Pressure (PSF)
Negative Zone 4	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Negative Zone 5	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Positive Zone 4&5	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF

		(AREA A, B, C)		
		ROOF	Surface Pressure (PSF)	Surface Pressure (PSF)
Negative Zone 1	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Negative Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Positive All Zones	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 2	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Overhang Zone 3	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
		(AREA A, B, C)		
		WALL	Surface Pressure (PSF)	Surface Pressure (PSF)
Negative Zone 4	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Negative Zone 5	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF
Positive Zone 4&5	10 SF	50 SF	100 SF	100 SF
	20 SF	20 SF	20 SF	20 SF
	30 SF	30 SF	30 SF	30 SF
	40 SF	40 SF	40 SF	40 SF
	50 SF	50 SF	50 SF	50 SF

- F. SEISMIC LOADS
1. AREA D:
- The seismic loads used in the strength design of the building frame shall be based on the general building code referenced above. The seismic load constants are as follows:
- S_{DS} = 0.285
- S_{D1} = 0.198
- Site Class = C
- Seismic Design Category = C
- Seismic Importance Factor = 1.25
- Basic Structural System: Building Frame Systems
- Seismic Resisting System: Steel Ordinary Concentrically Braced Frames
- R = 3.25
- C_u = 2.5
- C_u = 1.75
- Base Shear =
- Analysis Procedure: Equivalent Lateral Force
2. AREA D:
- The seismic loads used in the strength design of the building frame shall be based on the general building code referenced above. The seismic load constants are as follows:
- S_{DS} = 0.285
- S_{D1} = 0.198
- Site Class = C
- Seismic Design Category = C
- Seismic Importance Factor = 1.25
- Basic Structural System: Building Frame Systems
- Seismic Resisting System: Steel Ordinary Concentrically Braced Frames
- R = 3.25
- C_u = 2.5
- C_u = 1.75
- Base Shear =
- Analysis Procedure: Equivalent Lateral Force

3. AREA A, B, C: (PEMB)
- The seismic loads used in the strength design of the building frame shall be based on the general building code referenced above. The seismic load constants are as follows:
- S_{DS} = 0.285
- S_{D1} = 0.198
- Site Class = C
- Seismic Design Category = C
- Seismic Importance Factor = 1.25
- Basic Structural System: Building Frame Systems
- Seismic Resisting System: Steel Ordinary Moment Frames
- R = 3.5
- C_u = 3
- C_u = 3
- Base Shear =
- Analysis Procedure: Equivalent Lateral Force
4. AREA A, B, C: (PEMB)
- The seismic loads used in the strength design of the building frame shall be based on the general building code referenced above. The seismic load constants are as follows:
- S_{DS} = 0.285
- S_{D1} = 0.198
- Site Class = C
- Seismic Design Category = C
- Seismic Importance Factor = 1.25
- Basic Structural System: Building Frame Systems
- Seismic Resisting System: Steel Ordinary Moment Frames
- R = 3.5
- C_u = 3
- C_u = 3
- Base Shear =
- Analysis Procedure: Equivalent Lateral Force

FOUNDATION - GENERAL

- A. GEOTECHNICAL REPORT
- Foundation design is based on the geotechnical investigation (soil report) as follows:
- REPORT OF GEOTECHNICAL ENGINEERING SUBSURFACE CHARACTERIZATION
- OWENSBORO, KENTUCKY
- PROJECT: 2305-010 SHE
- VECTOR ENGINEERS, INC.
- MAY 27, 2023
- The soil report is available to the General Contractor upon request to the Owner. The information included therein may be used by the General Contractor for his general information only. The Architect and Engineer will not be responsible for the accuracy or applicability of such data therein.
- B. FOUNDATION APPROVAL AND INSPECTION BY GEOTECHNICAL ENGINEER
- Unless authorized otherwise by the Owner or Architect, the General Contractor shall notify the Geotechnical Engineer for review of foundation bearing surface, inspection of foundation installation and foundation installation methods (including construction dewatering methods where required) and shall not place concrete prior to Engineer's approval.
- C. SLAB-ON-GRADE CONSTRUCTION
1. Specification. Unless specified otherwise, slab on grade construction shall follow the recommendations of Guide for Concrete Floor and Slab Construction ACI 302.1R.
2. Subgrade Preparation
- Areas containing slab on grade construction shall be stripped to sufficient depth to remove all vegetation, top soil, organic or other unsuitable materials.
 - Site excavated soil may not be used for slab on grade subgrade material without the approval of the Geotechnical Engineer.
 - All grade adjustments for slab on grade construction shall be accomplished with select fill as specified in these General Notes.
 - No slab on grade concrete shall be poured against a final prepared subgrade containing free water, ice, frost, mud or other unsuitable material.
3. Reinforcing Steel
- See the drawings for typical slab reinforcement requirements.
 - All welded wire fabric shall be furnished in flat sheets. Lap ends and sides one cross wire spacing plus 2" at splices.
 - Lap continuous slab on grade reinforcing steel 30 bar diameters at splices but not less than 12".
 - All reinforcing steel and welded wire fabric for slabs on grade shall be chaired with slab bolsters designed for support on soil to provide specified cover to reinforcing steel.
4. Construction and Control Joints. See details on the drawings for requirements of construction and control joints for slab-on-grade construction.
- D. SELECT FILL
1. Select fill material shall be placed in maximum 8" loose lifts and compacted to 98% of Standard Proctor Density (ASTM D698) at 2% of optimum moisture. General Contractor to verify with Geotechnical Engineer.

AUGERCAST PILE FOUNDATION

- A. FOUNDATION SYSTEM
- These Contract Documents have been prepared using an augercast pile foundation with a capacity and depth as specified below.
- B. PILE CAPACITY AND LENGTH
1. Pile Capacity. The pile capacity shall be 100 Tons working load as indicated on the plans.
2. The length of the piles shall be 65 feet in length as indicated on the plans.
- C. PILE SIZE
- Augercast piles shall be 16 inches in diameter. See plans for reinforcing.

CONCRETE

- A. CLASSES OF CONCRETE
- All concrete shall conform to the requirements as specified in the table below unless noted otherwise on the drawings.
- | USAGE | STRENGTH (PSI) | TYPE | MAX. SIZE | AGG. | REMARKS |
|------------------------------------|----------------|------|-----------|------|-----------|
| 1. Footings | 4000 | NW | 1 1/2" | | |
| 2. Slab on Grades, Found. Walls | 4000 | NW | 1" | | |
| 3. Piers, Supporting Steel Columns | 4000 | NW | 1" | | |
| 4. Micropiles | 4000 | NW | 1" | | GROUT MIX |
- Notes: NW = Normal weight concrete
LW = Light weight concrete
All concrete shall be proportioned for maximum allowable unit shrinkage of 0.03% at 28 days as determined by ASTM C157.
- B. CONCRETE MIX DESIGNS
1. Engineer Approval. Concrete mix designs must be submitted a minimum of 15 days prior to the start of the work for Engineer and Owner's testing laboratory approval prior to placement of concrete in the plant or field. Any adjustments in approved mix designs including changes in admixtures must be submitted in writing to the Engineer and Owner's testing laboratory for approval prior to use in the field.

REINFORCING STEEL

- A. SPECIFICATION
- Reinforcing Steel. All reinforcing steel shall conform to the Specification for Deformed and Plain Billet Steel Bars for Concrete Reinforcement, ASTM A615 Grade 60 unless noted otherwise on the drawings. All reinforcing steel required to be welded shall conform to ASTM A706 Specification for Low Alloy Steel Deformed Bars for Concrete Reinforcement.
 - Welded Wire Fabric. Welded smooth wire fabric for concrete reinforcement shall conform to the Specification for Welded Steel Wire Fabric for Concrete Reinforcement, ASTM A185 with a yield strength of 65,000 PSI. Welded deformed wire fabric for concrete reinforcement shall conform to the Specification for Welded Deformed Wire Fabric for Concrete Reinforcement, ASTM A497 with a yield strength of 70,000 PSI. All welded wire fabric shall be furnished in flat sheets only.
 - Wire. Smooth wire for spiral reinforcement shall conform to the Specification for Cold Drawn Wire for Concrete Reinforcement, ASTM A82 with a minimum yield strength of 70,000 PSI.
 - Lap splices shall be Class A unless noted otherwise.
- B. REINFORCING STEEL COVERAGE
- Reinforcing steel coverage should conform to the requirements specified below. Cover specified shall be considered minimums that may require increasing where reinforcing steel intersects for different member types. Cover in structural members not specified below shall conform to the requirements of ACI 318 unless specified otherwise on the drawings.
- Foundation Members
 - Basement Walls - 2" dirt face, 1/2" interior face, unless noted otherwise
 - Foundation Walls - 2" both faces
 - Sump Walls, PI Walls - 2" both faces
 - Footings - 3" bottom and sides, 2" top
 - Interior Slab on Grade - 1" top cover, 3" bottom cover for two layers of steel
 - Exterior Slab on Grade - 1" top cover, 3" bottom cover for two layers of steel

CONCRETE MASONRY

- A. CODES AND SPECIFICATIONS
- All concrete masonry construction shall conform to the requirements of the local building code cited in these General Notes and the following codes:
- Building Code Requirements for Concrete Masonry Structures, ACI 530-13.
 - Standard Building Code Requirements for Masonry Construction, The Masonry Society.
- B. HOLLOW LOAD BEARING CONCRETE MASONRY UNITS
- Unless noted otherwise on the Architectural Drawings or Specifications, all concrete block walls shall utilize hollow load bearing units (CMU) conforming to ASTM C90 Hollow Load Bearing Concrete Masonry Units, Type 1, Grade N. Unless specified otherwise, CMU shall be cured by autoclave treatment at a minimum temperature of 350 F and a minimum pressure of 125 psi, or cured in a moisture controlled atmosphere as specified for Type 1 units. The Contractor shall furnish all required size and shapes as required to complete the work.
- C. GROUT
- Grout for masonry construction shall comply with the requirements of ASTM C476, Standard Specification for Mortar and Grout for Reinforced Masonry.
- Fine Grout. Fine grout containing sand, Portland cement and lime (lime is an optional ingredient) without coarse aggregate shall be used in grout spaces less than 2" in any horizontal direction unless otherwise specified.
 - Coarse Grout. Coarse grout containing sand, Portland cement, lime (lime is an optional ingredient), and coarse aggregate shall be used in grout spaces 2" or more in the least horizontal dimension unless indicated otherwise.
 - Strength. Grout shall attain a minimum 28 day compressive strength of 2800 psi using 3/4"x3/4"x7" or 3"x3"x6" test specimens cast in molds with a flat non-absorbent base and masonry units having the same moisture condition as those being laid forming the sides of the specimens. Specimens shall be capped according to ASTM C617 and tested according to ASTM C39.
- D. PRISM STRENGTH
1. Compressive Strength, f_m .
The compressive strength of masonry construction, f_m shall be as indicated below:
- Class of Masonry
- a. Single Wythe Hollow Masonry
- 2000 PSI
- Prism Tests. Prism tests shall be made for each class of masonry on the project using an assembly of actual masonry units, mortar and grout as planned in the work. Tests shall be run according to the requirements of ASTM E447. Test Methods for Compressive Strength of Masonry Prisms.
- E. HORIZONTAL JOINT REINFORCING AND TIES
1. Specification. All horizontal joint reinforcing and ties shall be built-welded wire units fabricated from cold drawn steel wire complying with ASTM A82 Cold Drawn Steel Wire for Concrete Reinforcement. Fabricated units shall have deformed continuous side rods and plain cross rods and shall be fabricated in straight lengths of not less than 10 feet. Out-to-out width of units shall be approximately 2" less than the nominal width of the wall positioned so that side rods have full embedment in mortar with mortar coverage of not less than 5/8" on joint faces exposed to the exterior and not less than 1/2" elsewhere. All units shall be fabricated from 9 gauge rods minimum unless noted otherwise. Exterior walls shall have hot dip galvanized after fabrication to comply with ASTM A153, Class B-2 coating (1.5 oz. per sq. ft.). Interior walls in conditioned space shall have units that are mill galvanized according to ASTM 641 Class 3. Prefabricated matching corner (L) and intersecting (T) sections shall be used to form continuous reinforcement around all corners and for anchoring abutting walls and partitions.
2. Single-Wythe Masonry Walls. All single-wythe masonry walls shall be reinforced with ladder type or truss type units with a single pair of side rods and continuous diagonal or perpendicular cross rods attached to side rods no further apart than 16" on center. Units shall be spaced in the wall at not more than 16" on center vertically.
3. Brick and Block Cavity Wall. All brick and block cavity walls shall be reinforced with ladder or truss type units in the back-up block wall having a single pair of side rods and continuous diagonal or perpendicular cross rods attached to side rods not further apart than 16" on center. Units shall be spaced in the block wall at not more than 16" on center vertically. The outer brick wythe shall be tied to the block back-up wall with rectangular type adjustable wall ties manufactured from 3/16" diameter wire hot dip galvanized to comply with ASTM A153, Class B-2 coating (1.5 oz. per sq. ft.). One wall tie shall be provided for each 2-8 square feet wall area spaced not further apart than 16 inches vertically and 24" horizontally. Wall ties shall be placed in alternate courses from block wall horizontal reinforcing. Bed joints of opposing wythes shall be not further apart vertically than 12" either direction. Ties shall be sized to extend a minimum of 2" into the brick and block joints.
4. Additional Reinforcement at Top and Bottom of Walls. Provide horizontal wall reinforcement in the bed joint of the second course and top course of masonry in addition to the typical reinforcing specified above.
5. Additional Reinforcement at Wall Openings. Provide additional horizontal reinforcing in the first and second bed joints 8" apart immediately above lintels and below sills of all openings. Such reinforcement not otherwise continuous shall extend a minimum of two feet past the opening on each side. Horizontal wall reinforcement interrupted by the jamb of an opening shall have the cross rod or side rod bent and hooked at the jamb. Provide an additional reinforcement adjustable tie at the jamb for each joint containing the normal horizontal reinforcing unit.
6. Splices in Horizontal Wall Reinforcing. Horizontal wall reinforcing shall be spliced a minimum of 6" at splices.

- F. STABILITY AND BRACING OF MASONRY WALLS DURING CONSTRUCTION
- All masonry walls shown on the architectural and structural drawings have been designed to resist the required code vertical and lateral forces applied to them in the final constructed configuration only assuming full bracing top, bottom, and/or side of wall as shown. It is the responsibility of the Contractor to properly and adequately brace all masonry walls at all stages during construction to resist erection loads and lateral loads that could possibly be applied prior to completion of construction.

ANCHOR RODS

- A. SPECIFICATION
- All anchor rods shall be made from threaded round stock conforming to ASTM F1554, Grade 36 steel unless indicated otherwise in the column schedule or detailed on the drawings. Grade 36 anchor rods shall conform with the ASTM F1554 S1 Supplemental Requirements for Weldability.
 - Anchor rods shall conform to ASTM F1554, S4 and S5 requirements for toughness.
- B. NUTS
- All nuts with anchor rods shall be hex head conforming to ASTM Specification A563, Grade A (Grade D or DII for Grade 105 Anchor Rods).
- C. WASHERS
- Washers for all base plates shall be as specified by AISC.
- D. TEMPLATES
- All anchor rods set in concrete shall utilize 1/8" thick steel templates same size as the base plate. Templates shall be detailed on the shop drawings.
- E. MINIMUM ANCHOR ROD SIZE
- Unless indicated otherwise in the Column Schedule or on the drawings, anchor rods shall be ASTM F1554 steel and size shall be 1/2" diameter (1"0" minimum embedment).

NON-SHRINK GROUT FOR BASE PLATES AND BEARING PLATES



- A. TYPE
- Grout for base plates and bearing plates shall be a non-metallic, shrinkage resistant, premixed, non-corrosive, non-staining product containing Portland cement, silica sand, shrinkage compensating agents and fluidity improving compounds.
- B. SPECIFICATIONS
- Non-shrink grout shall conform to Corps of Engineers Specification for Non-Shrink Grout, CRD-C621-83.
- C. COMPRESSIVE STRENGTH
- Twenty-eight day compressive strength as determined by grout cube tests, shall be 8,000 PSI.
- D. PLACEMENT
- Grout shall be placed in a fluid flowable state under baseplates that have a form built around them for grout confinement. Grout should be cured according to manufacturer's recommendations.
- E. MINIMUM THICKNESS
- Minimum thickness of grout under all baseplates and bearing plates shall be 1 1/2", unless specified otherwise on the drawings.

STRUCTURAL STEEL


- A. SPECIFICATIONS
- The design, fabrication and erection of all structural steel shall conform to the following:
- Specification for Structural Steel Buildings latest edition, published by the American Institute of Steel Construction (AISC).
 - Detailed for Steel Construction as published by AISC.
 - Engineering for Steel Construction as published by AISC.
 - Code of Standard Specifications for Steel

CONCRETE MASONRY UNIT (CMU) LOAD BEARING WALL SCHEDULE

1.  INDICATES WALL SIZE AND REINFORCING.
2. REINFORCING SHALL BE LOCATED IN CENTER OF WALL, UNLESS NOTED OTHERWISE.
3. CELLS WITH REINFORCING SHALL BE GROUTED SOLID, FULL HEIGHT.
4. ALL NON-LOADBEARING CMU (8" OR 8") SHALL BE REINFORCED WITH #4 AT 48" O.C., UNLESS NOTED OTHERWISE. (SEE SCHEDULE)
5. ALL CMU BELOW GRADE SHALL BE GROUTED SOLID.
6. SEE TYPICAL DETAILS FOR ALL OTHER INFORMATION.
7. FLUSH WALL PLASTERS SHALL CONTAIN REINFORCING AS SHOWN BELOW. BARS SHALL BE CENTERED IN EACH CELL. MINIMUM LENGTH OF PLASTERS SHALL BE 1'-4", UNLESS NOTED OTHERWISE. UNLESS PLASTER NOTED OTHERWISE ON PLANS, REFER TO DETAILS 6. 7. 11 / S3.0.
8. SEE SHEARWALL DETAIL 14S3.0 FOR ADDITIONAL INFORMATION REGARDING ALL SHEARWALLS. UNLESS NOTED OTHERWISE, ALL LOAD BEARING CMU/STRUCTURAL WALLS SHALL BE CONSIDERED SHEARWALLS.
9. ALL VERTICAL REINFORCING BARS SHALL BE POSITIONED UTILIZING BAR POSITIONERS TO ENSURE PROPER LAP SPLICE AND LOCATION.
10. SEE 12S3.0 FOR TYPICAL CMU WALL CONSTRUCTION. PROVIDE BOND BEAMS AT 4'-0" (MAX.) ON CENTER VERTICALLY. 8" CMU TO RECEIVE 2-#4 CONT. BARS AND 10" & 12" CMU TO RECEIVE 2-#5 CONT. BARS.

MARK	CMU SIZE	VERTICAL REINFORCING	BOND BEAM	REMARKS
 CMU1	12"	#6 AT 32" ON CENTER	2 - #5S	
 CMU2	8"	#5 AT 24" ON CENTER	2 - #4S	

STRUCTURAL LINTEL SCHEDULE (SL)



MARK	TYPE	LINTEL / PLATE SIZE	REMARKS
SL-1	A1	WB24 W/ 1 1/4"x11" BTM. PL.	
SL-2	A1	WB24 W/ 1 1/4"x11" BTM. PL.	
SL-3	A2	WB40 W/ 1 1/4"x11" TOP PL.	

- NOTES:
- WHEN SPAN EXCEEDS 6'-0" SHORE THE LINTEL DURING CONSTRUCTION.
 - GROUT ALL CMU CELLS SOLID TO 1'-4" ABOVE THE LINTEL.
 - FOR TYPE B & C LINTEL, USE BRICK TIES AT 1'-4" O.C. TACK WELD TO BEAM WEB.
 - BEAM PLATES SHALL EXTEND OPENING EDGE TO OPENING EDGE.
 - BEARING LENGTH ON EACH END SHALL EQUAL 1/12 x LINTEL SPAN (IF MIN.), INSTALL ON FRESH MORTAR BED.
 - WELD PLATES W/ MIN. 3/16" FILLET WELD, 3" LONG, AT 12" O.C. (TYP. MIN. WELD)
 - ALL LINTELS EXPOSED TO THE EXTERIOR SHALL BE GALVANIZED.
 - SEE THE ARCHITECTURAL PLANS AND THE STRUCTURAL PLANS FOR LOOSE STEEL LINTELS (LL) AS MAY BE REQUIRED TO SUPPORT FACE BRICK AND OTHER NON-LOAD BEARING MASONRY.

LOOSE STEEL (LL) LINTEL SCHEDULE


WALL TYPE	NOMINAL WALL THICKNESS	CLEAR MASONRY OPENING WIDTH	STEEL LINTEL SECTION
BRICK	4"	UP TO 6'-4"	4"x3 1/2"x8 1/8"(LLV) ANGLE
		UP TO 7'-4"	5"x3 1/2"x8 1/8"(LLV) ANGLE
		UP TO 8'-4"	6"x3 1/2"x8 1/8"(LLV) ANGLE
		UP TO 11'-0"	6"x3 1/2"x12 1/2"(LLV) ANGLE
CONCRETE MASONRY UNIT (CMU)	6"	UP TO 7'-4"	2-3 1/2"x2 1/2"x8 1/8"(LLV) ANGLES
		UP TO 7'-4"	2-4"x2 1/2"x8 1/8"(LLV) ANGLES
	8"	UP TO 8'-4"	2-5"x2 1/2"x8 1/8"(LLV) ANGLES
		UP TO 11'-0"	2-6"x2 1/2"x8 1/8"(LLV) ANGLES
	10"	UP TO 9'-4"	2-6"x4"x8 1/8"(LLV) ANGLES
		UP TO 11'-0"	2-7"x4"x8 1/8"(LLV) ANGLES
	12"	UP TO 9'-4"	3-4"x2 1/2"x8 1/8"(LLV) ANGLES
		UP TO 11'-0"	3-6"x2 1/2"x8 1/8"(LLV) ANGLES

- NOTES:
- LINTELS CALLED OUT ON THIS SCHEDULE ARE FOR NON-LOAD BEARING MASONRY WALLS AND ARE FOR LOAD BEARING MASONRY WALLS WHERE STEEL LINTEL IS NOT REFERENCED AND THE LOAD IS INTRODUCED ABOVE THE LINTEL AT A DISTANCE GREATER THAN THE LINTEL SPAN.
 - CMU IS MASONRY MATERIAL COMPLYING WITH THE ASTM C90 SPECIFICATION. ALL CMU MATERIAL SHALL BE NORMAL WEIGHT UNLESS NOTED OTHERWISE.
 - PROVIDE MINIMUM 8" BEARING EACH END OF LINTEL. LINTEL BEARING LENGTH SHALL BE 1/12 LINTEL CLEAR SPAN.
 - ALL LINTELS EXPOSED TO THE EXTERIOR SHALL BE HOT-DIPPED GALVANIZED UNLESS NOTED OTHERWISE. ALL OTHER LINTELS SHALL BE PAINTED.
 - WHEN THE LINTEL CLEAR SPAN EXCEEDS 7'-4", SHORE THE LINTEL AT 4'-0" O.C. (MAX.) UNTIL ALL MORTAR AND GROUT HAVE REACHED 75 PERCENT OF SPECIFIED COMPRESSIVE STRENGTH.
 - CONTROL JOINTS AT MASONRY OPENINGS UTILIZING THE LOOSE STEEL LINTELS ON THIS SCHEDULE SHALL CONFORM TO THE TYPICAL DETAILS.
 - ANY LINTEL CONDITIONS NOT COVERED BY THIS SCHEDULE SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER.

NON LOAD BRG. CMU REINF. SCHEDULE

NOM. CMU THICKNESS	REINFORCEMENT		REMARKS
	VERTICAL	BOND BEAM	
8" NON-LOAD-BEARING	#4 @ 48" O.C.	2-#4 CONT.	
10" NON-LOAD-BEARING	#4 @ 48" O.C.	1-#4 CONT.	



- NOTES:
- BOND BEAM REINFORCING DOES NOT REQUIRE HOOKS AT ENDS FOR NON-LOAD BEARING WALLS. U.N.O.
 - ALL NON-LOAD BEARING TOP OF WALLS TO BE BRACED AT 36 x NOMINAL WALL THICKNESS. IF INTERSECTING WALLS EXCEED SPACING, BRACE ACCORDINGLY.



- NOTES:
- ALL ANCHOR RODS SHALL BE ASTM F1554 GRADE 36.
 - HEADED BOLT OR THREADED STOCK MATERIAL MUST BE USED FOR ANCHOR RODS.

④ Typical Anchor Rod Detail
1" = 1'-0"

SHERMAN
CARTER
BARNHART
ARCHITECTS



OWENSBORO INDOOR
SPORTS FACILITY
SCHEDULES AND TYPICAL
DETAILS

SCHEDULES AND TYPICAL
DETAILS

JOB NO.	22070
DATE	MAY 20, 2024
DRAWN	STAFF
CHECKED	TEL
COPYRIGHT © 2024 SHERMAN CARTER BARNHART ARCHITECTS PLLC	

REVISIONS	

SHEET

S0.2